PEC LTD.
21 Shipyard Road, Singapore 628 144
Tel: 6268 9788 Fax: 6268 9488
URL: http://www.peceng.com

DISTRIBUTION	
INTERNAL	
HEAD OFFICE	
SITE OFFICE	
EXTERNAL	
CLIENT	1
CONSULTANT	
SUB CON .1	
SUB CON .2	
SUB CON .3	
TOTAL	1
PURPOSE	
INFORMATION	
PRELIMINARY	
TENDER	√
COMMENT	
REVIEW	
APPROVAL	
CONFIRMATION	
CONSTRUCTION	
AS-BUILT	

DATASHEET FOR TELESCOPIC BELT CONVEYOR

Project:

GRASSROOT LUBE COMPLEX PROJECT AT AMMULAVAYOL, CHENNAI

Consultant:

PEC LTD.

Client:

INDIAN OIL CORPORATION LIMITED

	Total No. of Sheets	Page
	04 (Incl, cover sheet)	Page 1 of 04

REV.	DESCRIPTION	PREP BY	CHK BY	TECH APP	PROJ APP	DATE
A	ISSUED FOR TENDER	HTO	SBS	DR	KGK	21/02/21

TITLE: DATASHEET FOR TELESCOPIC BELT CONVEYOR

PEC PROJECT NO.	EPS JOB NO.	IOC JOB NO.	DOCUMENT NO.	SIZE	REV.
0RG2N0410000	0RG2N0410000	HCC/LUBES-07/GT-09/2018-19 (E-Tender ID: 2018_MKTHO_80987_1)		A4	A

DATASHEET FOR TELESCOPIC BELT CONVEYOR

Sr.No.	ITEMS	Description
	SCOPE	Design, Engineering, drawing approval, procurement, fabrication/manufacture, assembly, testing, supply, installation assistance and commissioning of Telescopic Belt conveyors
	SERVICE	For use in : a) Packaging material Warehouse – for unloading of packaging materials from Trucks for storage in Warehouse (viz. Flat Cartons, Stacks of Pails, Carton boxes of Caps etc.) - 1no. b) Finished product warehouse – for Loading of FP cartons for small packs / Filled pails etc. into Trucks – 2nos The units are for Indoor application but due to the coastal weather conditions – environment is highly corrosive in nature; Painting specifications to consider these factors; To consider highly corrosion resistant Epoxy or equivalent paint of required DFT.
	PROJECT SITE	Amullavoyal village at Chennai . Tamil Nadu State The requirement is for a Greenfield, Grassroot Lube Complex – being set up at Chennai;
1.	Quantity	3 Nos.
2.	Material To Be Handle	Boxes / Flat Carton bundles / Stacks of Pails etc. as mentioned above.
3.	Weight Of The Box/Bags	25-40 Kg. Maximum
4.	Size Of Box/Bags	600 (L) x 500 (W) x 600 (H) (OVERALL)
5.	Temperature	Ambient
6.	Capacity	550 Boxes Per Hour
7.	Type	Collapsible Boom Type Hinged Telescopic Belt Conveyor;
8.	Design Capacity	600 Per Hour

9.	Size Of Belt	750 mm Width
10.	Type Of Belt	Rough Top 2 Ply, PVC Coated Endless Type
11.	Length Of Conveyor	Fixed Length : 4800 mm Telescopic (Expanded) : 6000 mm Total : 10,800 mm
12.	Main Body Of Conveyor	Manufacturing From IS 226 Plate Material - VTC
13.	Snub Pulley for Conveyor	VTC
14.	Drive Pulley	VTC
15.	Telescopic Movement	Mechanical Arrangement
16.	Mounting	On Fixed MS Chassis Mounted On Fabricated Frame with FIX and CASTOR Wheel with Manual Toeing Bar
17.	Height Adjustment	With 2 HP Power Pack & Cylinder for Height Adjustment (All components to be of reputed make - VTC makes of components)
18.	Panel	The Conveyor comes with a Fixed Main Panel on Rear Side and Front Side Only; Operating Panel with Emergency Stopper Sensor Bar, LED Lighting, Totally Consoled Wiring.
19.	Painting	INTERNAL : High corrosion resistant Epoxy paint of required DFT as per Vendor standard; VTC;
	DRIVE FOR BELT	**SPECIFICATION**
1.	Belt Motor	** HP, 1440 RPM, TEFC – VTC details of Make, type etc.
2.	Motor Make	Rotomotive or suitable equivalent make – VTC
3.	Gear Box	Worm Type, Wall Mounted , With Suitable Ratio - VTC
4.	Gear Make	Rotomotive or suitable equivalent make -

		VTC
	DRIVE FOR TELE. MOVEMENT	**DESCRIPTION**
1.	Motor	** HP, 1440 RPM, TEFC- VTC make, HP and Type;
2.	Motor Make	Rotomotive or suitable reputed equivalent make – VTC
3.	Gear Box	Worm Type, Wall Mounted , With Suitable Ratio – VTC
4.	Gear Make	Rotomotive or equivalent – VTC
	DRIVE FOR TRANSVERSE MOVEMENT	**CROSS TRANSVERSE LENGTH 10.8 MTR**
1.	Motor	** HP – VTC make, HP, RPM and Type;
2.	Motor Make	Rotomotive or Equivalent – VTC
3.	Gear Box	Worm Type, Wall Mounted , With Suitable Ratio – VTC
4.	Gear Make	Rotomotive or suitable reputed equivalent make - VTC
	ACCESSORIES	The unit shall be complete with all necessary accessories – required for normal operation & Maintenance of the machine; To ensure safety of personnel at the time of working suitable arrangements to be provided in the design, in such a manner and location as necessary to give safe and complete access to all the parts of the machine requiring inspection or adjustments.
	DOCUMENTATION	Vendor to confirm that following documentation will be submitted in 3 sets on placement of PO: -General Arrangement drawing - Installation drawing -Equipment layout and static loads - Guarantee / Warranty Certificate -Manufacturer's original Test Certificates & Guarantee certificates for bought out components - Inspection / Performance Test report for the unit - Installation manual - Operations & Maintenance manual