**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Suroj Buildcon Pvt Ltd.**
Bungalow No. 3, Liberty Society Phase-I,
North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

**Date : 23.06.2020**
**Quote NO : SQT/19-20/2621**
**Kind Attn : Mr.Nikhil Bakane**
**Email Id :** nbakane@suroj.in
**Contact No: 020 4135 5926**

**Subject : Quotation for Rolling Shutter.( Project Location - Madepura electric locomative pvt ,Ajni, Nagpur )**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Motorized Rolling Shutter** | 4000 | 3600 | 2 | 174,000 | 348,000 | 20,000 | 40,000 |
| 2 | **Motorized Rolling Shutter** | 2500 | 3600 | 1 | 144,000 | 144,000 | 20,000 | 20,000 |
| 3 | **Motorized Rolling Shutter** | 3600 | 3600 | 2 | 166,000 | 332,000 | 20,000 | 40,000 |
| 4 | **Motorized Rolling Shutter** | 3000 | 4000 | 1 | 160,000 | 160,000 | 20,000 | 20,000 |
| 5 | **Motorized Rolling Shutter** | 3000 | 3600 | 3 | 154,000 | 462,000 | 20,000 | 60,000 |
| 6 | **Dock Leveller** | 2000 | 2500 | 2 | 250,000 | 500,000 | 20,000 | 40,000 |
| | | | **Total** | | | **1,946,000** | | **220,000** |
| 7 | P&F Charges | | | 3% | | 58,380 | | |
| | **Total Without Taxes** | | | | | 2,004,380 | | 220,000 |
| | GST Extra @ 18% | | | 18% | | 360,788.40 | | 39,600 |
| | **Total With Taxes** | | | | | **2,365,168** | | **259,600** |
| 8 | Transportation Charges | | | | | In Client Scope | | |
| 9 | Unloading Charges @ Site | | | | | In Client Scope | | |
| | **Optional Accesaries** | | | | | | | |
| 10 | **Hood Cover + Motor Cover** | | | 1 | 15,000 | 15,000 | | |
| 11 | **Three Station Push Button** | | | 1 | 10,500 | 10,500 | | |

NIHVA TECHNOLOGIES PVT. LTD.

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr .No. | Specification | GI Motorized Rolling Shutter |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with GI Laths with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick MS. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener |
| 12 | **Surface finish** | PU paint or Powder coated |
| 13 | **Drive Unit & Mounting Type** | Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection |
| 14 | **Rubber seal at bottom & Grill** | Included |

**Technical Specification**

| Description | Dock Leveller |
|---|---|
| **Capacity** | 6 Ton |
| **Dock operation mode** | AC power pack hydraulically operated |
| **Lip operation mode** | Hydraulic |
| **Operation control** | Through panel |
| **Loading platform height from road** | 1250mm |
| **Travel above & below dock level** | (+) 300 / (-) 250 mm |
| **Platform Size (W x L)** | 2000 mm x 2500 mm |
| **Lip size (W x L )** | 2000 x 400 mm |
| **Shut Height** | 480 mm |
| **Overall length** | 2000mm x 2500mm + Lip Length (400mm ) |
| **Maximum slope can be achieved** | 10% |
| **Clear Pit dimensions (W x L x D)** | (W) 2050mm x (L) 2050 mm x (D)485 mm |
| **Hydraulic power pack** | Standard |
| **Driver type** | Direct by electric Motor |
| **Motor Ratings** | 1 H.P |
| **Pump design flow** | 2.5 LPM |
| **Pump pressure** | 120 bar Operating 200 bar Max. |
| **Safety valve set pressure** | 120 Kg/cm$^2$ |
| **Pump Type** | Gear |
| **Volume of oil receiver** | 7 Lit |
| **No Of Deck cylinder** | 2 No |
| **Lip Cylinder** | 1 No |
| **Dock Bumper** | Pair of Dock Bumper |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Bahvin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd