**BOQ**

**Name of Contractor :** Nihva Technologics Pvt Ltd **Date:** 01.12.2025

**Name of Work:- Replacement of dome double wall sheet with new polycarbonate sheet at FID, ARAI, Chakan, Pune.**

| Sr. No. | Description of Item | Unit | Qty. | Rate | Amount |
|---|---|---|---|---|---|
| 1 | **Replacement of existing dome double wall sheet with providing and fixing 3mm solid Polycarbonate sheet** ( Make: Palaram, Lexan, Palsun, Tilara, Durotuff, PC Lite or equivalent-**10 year warranty** ) including installation **over existing MS frame structure** including all accessories required for installation- Powder coated Aluminium Profile, EPDM, weatherseal Seleant etc all complete. Approx. Size is as per drawing attached. **(Scope also include removing and disposal of existing dome double wall sheet outside ARAI premises)**. Polycarbonate colour shed as per ARAI Engineer-In charge directions. | Nos | 1.00 | 491700 | 491700 |
| | | | | | |
| | **Total Basic Amount** | | | | 491700**/-** |
| | Add CGST 9% | | | | 44253/- |
| | Add CGST 9% | | | | 44253/- |
| | **Total Amount** | | | | 580206/- |

**Special Note :** Please follow all safety norms and provided all necessary safety PPE to Workers while execution as per type of work.

**Authorised Signature & Stamp**