**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Date : 30.12.2020**
Quote NO : SQT.20.21.2909 R
**Kind Attn : Mr. Virendra Gaikwad**
Email Id : Virendra.Gaikwad@schreiberfoods.com
Contact No : 9158894809

**Schreiber Dynamix dairies Pvt.Ltd**
Baramati

**Project Name & Location: Baramati**

**Subject : Quotation for Sectional Door, Dock Leveler, Dock Shelter**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 4 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Assa Abloy Sweden make Dock Shelter** | 3400 | 3400 | 1 | 98,000 | 98,000 | Inclusive | |
| | | | | **Total** | | **98,000** | | - |
| 2 | P&F Charges | | | 3% | | **2,940** | | |
| | **Total Without Taxes** | | | | | **100,940** | | - |
| | GST Extra @ 18% | | | 18% | | 18,169 | | - |
| | **Total With Taxes** | | | | | **119,109** | | - |
| 3 | Transportation Charges | | | | | **Extra at Actual** | | |
| 4 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**ASSA Abloy - Crawford Make Retractable Dock Shelter**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | **Size** | (W) 3400 mm x (H) 3400 mm |
| 2 | **Top Curtain** | 1000 mm |
| 3 | **Side Curtain** | 600 mm |
| 4 | **Curtain colour** | Black |
| 5 | **Parking Guides** | White, Yellow |
| 6 | **Wall Fixings** | Concrete, Sandwich light Concrete, Load house cavity, insulated panel |
| 7 | **Top & Side Curtaiins** | Double Layer High Quality Polyester |
| 8 | **Thickness** | 3.0 mm |
| 9 | **Weight** | Approx 3400 g/m2 |

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault
Showroom, Thermax chowk, MIDC,
Chinchwad.

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | |
| 4 | Any civil / masonry/structural work required | |
| 5 | All structure support required | |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | |
| 7 | Conduits, Cables required | |
| 8 | Steel structure for Dock House & Sectional Door | |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 1-2 Weeks from the date of receipt of confirmed order, advance payment and drawing approval

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd