NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Haldiram Food International
Nagpur

Project, Location : Nagpur

Date : 11.03.2021
Quote NO : SQT.20.21.3094R
Kind Attn : Abhay Kendhe
Email Id : abhay.kendhe@haldirams.com
Contact No: 9765189120

Subject : Quotation for Motorized Single Skin Rolling Shutter and Gear Operated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option I	Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorised Single Skin Rolling Shutter**	2380	2950	9	93,000	837,000	12,000	108,000
2	**Motorised Single Skin Rolling Shutter**	4000	3000	4	116,000	464,000	12,000	48,000
3	**Motorised Single Skin Rolling Shutter**	4000	4000	9	136,000	1,224,000	12,000	108,000
4	**Motorised Single Skin Rolling Shutter**	2500	3000	1	95,000	95,000	12,000	12,000
5	**Motorised Single Skin Rolling Shutter**	4000	3000	4	116,000	464,000	12,000	48,000
	Total			**27**		**3,084,000**		**324,000**
6	P&F Charges			3%		92,520		
	Total Without Taxes					3,176,520		324,000
	GST Extra @ 18%			18%		571,774		58,320
	Total With Taxes					**3,748,294**		**382,320**
7	Transportation Charges					**In NIHVA Scope**		
8	Unloading Charges @ Site					In Client Scope		

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option II	Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Gear Operated Rolling Shutter**	2380	2950	9	72,000	648,000	12,000	108,000
2	**Gear Operated Rolling Shutter**	4000	3000	4	97,000	388,000	12,000	48,000
3	**Gear Operated Rolling Shutter**	4000	4000	9	117,000	1,053,000	12,000	108,000
4	**Gear Operated Rolling Shutter**	2500	3000	1	74,000	74,000	12,000	12,000
5	**Gear Operated Rolling Shutter**	4000	3000	4	97,000	388,000	12,000	48,000
	Total			**27**		**2,551,000**		**324,000**
6	P&F Charges			3%		76,530		
	Total Without Taxes					2,627,530		324,000
	GST Extra @ 18%			18%		472,955		58,320
	Total With Taxes					**3,100,485**		**382,320**
7	Transportation Charges					**In NIHVA Scope**		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm. **(FLAT - Slat)**
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm **(Semi Circle Shape)**
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Gear Operated Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description**	Gear Operated Rolling Shutter with GI slats with thickness of 1 mm. **(FLAT - Slat)**
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm **(Semi Circle Shape)**
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Mukesh Wasnik on 9325818035** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd