NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JINIS INTERNATIONAL PTE LTD
1 Soon Lee Street, #05-01 , Pioneer Centre
Singapore – 627 605

Date : 04.09.2019
Quote NO : SQT/19-20/2015
Kind Attn : Manu B
Email Id : sales@jinis.com.sg
Contact No: 84255660

Subject : Quotation for Turnstile and Flap barrier .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Single Sided Full Height Turnstile Gate			1	3,65,000	3,65,000	20,000	20,000
2	Dual Side Full Height Turnstile			1	5,95,400	5,95,400	20,000	20,000
3	FLAP BARRIERIER GATE			1	1,85,000	1,85,000	20,000	20,000
4	Controller			1	15,000	15,000		-
5	Card			1	30	30		-
6	Card Reader			1	5,000	5,000		-
				Total		**11,65,430**		**60,000**
7	P&F Charges			3%		34,963		
	Total Without Taxes					12,00,393		60,000
	GST Extra @ 18%			18%		2,16,070.72		10,800
	Total With Taxes					**14,16,464**		**70,800**
8	Transportation Charges					In Client Scope		
9	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Single Sided Full Height Turnstile Gate: • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatic ally in certain time, and the potency is small, will make an alarm sound at the same time. • Resengautomatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. lock time: 0.2s; Pass rate: 35 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w; Weight:220kgMake	
Double Sided Full Height TurnstileGate: • It has zero position of self -checking, easy for users to maintain and use. •There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatic ally.. • IR/mec hanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatic ally in certain time, and the potency is small, will make an alarm sound at the same time. • Resengautomatic ally: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • he whole system works steadily, and the noise is very low. nlock time: 0.2sPass rate: 70 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w Weight:400kg.	
FLAP BARRIER GATE : Size (L x B x H) - 1400 x 280 x 980 mm Unlock Time - 0.2 Sec Pass Rate - 35 person / min Pass Width - 550 mm Weight - 120 Kg Mode - Fail Safe Power Consumption - 30 W Driving voltage - 24 V	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat on 7219206333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd