NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Serum Institute
Pune

Date : 27.10.2020
Quote NO : SQT.20.21.2717R
Kind Attn : Mr. Pradip Paithane
Email Id : eeshwar.daundkar@seruminstitute.com
Contact No: 020-26602764

Project Name & Location:

Subject : Quotation for Automatic Telescopic Sliding Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Biparting Sliding Glass Door System**	2000	2530	1	2,35,000	2,35,000	15,000	15,000
2	**Automatic Telescopic Sliding Glass Door System**	2070	2400	1	4,25,000	4,25,000	15,000	15,000
				Total		**6,60,000**		**30,000**
2	P&F Charges on Total Supply Value			3%		**19,800**		
	GST Extra @ 18%			18%		**1,18,800**		**5,400**
3	Transportation Charges					**Extra at Actual**		
4	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Automatic Sliding Glass Door System

Sr. No	Description	Specifications
1	Motor	High performance and heavy duty DC motor with integrated encoder and gearbox
2	Power Supply	170-260 V AC 50-60 Hz
3	Power Consumption	170 W
4	Protection Class	IP 22
5	Carrying Capacity	170 Kg for single leaf, 240 Kg for double leaves
6	Operator Chassis Size	125 x 168 mm , Aluminium
7	Carrier Assembly	Two carrier assembly for each leaf, (2 main and 1 balancing wheel for each carrier assembly)
8	Trigger Belt	Special trigger belt design for maximum safety and endurance and minimum noise level
9	Working Temperature	- 20* C + 50* C
10	Position Selector	Digital , 6 user positions, LCD touch screen
11	User Modes	Auto , Open , In , Out , Locked , Partial Opening
12	Installer Settings	Opening Speed, Closing Speed, Hold Open Time, Half Opening Distance, Opening, Direction, Installer Password, User Password
13	Obstacle Detection	Permanent obstacle detection in both opening and closing cycles.
14	Energy Saving	Short braking distance during opening and closing cycle for energy saving
15	Interlocking	2 doors can be operated using interlocking mode
16	Resetting	Can be performed using digital position selector without opening operator cover
17	Compatibility	Compatible with fire alarm and access control systems
18	Fault Monitoring	Error codes are shown on the digital position selector screen.
19	Safety	3D infrared curtain photocell
20	Opening Sensor	Radar
21	Combiner (Opening + Safety) Sensor	Opening radar with integrated 3D infrared curtain photocell, Energy saving, EN16006
22	Door Leaf	Frameless With 2 point fittings per door panel
23	Glass	12mm thick Glass
24	Operator Mounting	On glass panel provided by others

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd