NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SERUM INSTITUTE OF INDIA PVT LTD
POONAWALLA BIOTECHNOLOGY PARK
Manjari BK, Tal. Haveli,
Pune 412 307.INDIA .

Date : 07.10.2020
Quote NO : SQT.20.21.2746
Kind Attn : Mr. Prafull Garad
Email Id : prafull.garad@seruminstitute.com
Contact No: 020 6762 6155

Project Name & Location: SERUM INSTITUTE OF INDIA PVT. LTD. Manjari.

Subject : Quotation for Pit Mounted Scissor Lift .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Scissor Lift**	(L) 1500 x (W) 2200	1	3,47,500	3,47,500	20,000	20,000
			Total		**3,47,500**		**20,000**
2	P&F Charges on Total Supply Value		3%		**10,425**		
	Total Without Taxes				**3,57,925**		**20,000**
	GST Extra @ 18%		18%		64,427		3,600
	Total With Taxes				**4,22,352**		**23,600**
3	Transportation Charges				**In Client Scope**		
4	Unloading Charges @ Site				**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Pit Mounted Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	3 ton
2	**Platform size**	1500(L) x 2200 (W)
3	**Shut ht**	600 mm
4	**Max ht**	1800 mm
5	**Lift ht**	1200 mm
6	**Power pack**	3HP, 3 Phase
7	**Safety Railing**	both length side only (900 mm height)
8	**Color**	as per req. RAL shade.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment :80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333.**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd