NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Afcons Infrastructure Limited
TechWeb Center, 6th Floor, New Link Road, Anand Nagar
Jogeshwari West, Mumbai, Maharashtra 400102

Date : 15.05.2021
Quote NO : **MHE_21.22.0009**
Kind Attn : Mr. Akshay Ghogale
Email Id : akshay.ghogale@afcons.com
Contact No: 9967778722

Project Name & Location: Telescopic Truck Loader/Unloader Conveyor, IOCL Project

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation considering 03 people for 03 days per conveyor in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor (20 ft truck)**	**3**	**16,31,520**	**48,94,560**	**75,000**	**2,25,000**
	Total			**48,94,560**		**2,25,000**
	P&F Charges	3%		**1,46,837**		
	Total Without Taxes			**50,41,397**		**2,25,000**
	GST Extra @ 18%	18%		**9,07,451**		**40,500**
	Total With Taxes			**59,48,848**		**2,65,500**
2	Transportation Charges					**Extra At Actual**
3	Insurance Charges					**Depend on Site**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Boxes / Flat Carton bundles / Stacks of Pails
2	Maximum Product Size	600 mm (L) x 500 mm (W) x 600 mm (H) (OVERALL)
3	Maximum Weight of Box/Bag	25-40 Kg. Maximum
4	Capacity	550 Boxes Per Hour
5	Temperature	Ambient
6	Type	Collapsible Boom Type Hinged Telescopic Belt Conveyor
7	Design Capacity	600 Per Hour
8	No. of Extension Stages	3
9	Basic Overall Height	900 mm
10	Size of Belt	750 mm Width
11	Belt Type	PVC Coated Endless Type
12	Length Of Conveyor	Fixed Length : 4800 mm Telescopic (Expanded) : 6000 mm Total : 10,800 mm
13	Main Body Of Conveyor	Manufacturing From IS 226 Plate Material - VTC
14	Snub Pulley for Conveyor	Nihva make
15	Drive Pulley	Nihva make
16	Telescopic Movement	Mechanical Arrangement
17	Mounting	On Fixed MS Chassis Mounted On Fabricated Frame with FIX and CASTOR Wheel with Manual Toeing Bar
18	Finish	RAL 5002 ultramarine blue or as per client's request Base coat of Zinc Chromate Primer 2 coats of finish paint
19	Height Adjustment	With 2 HP Power Pack & Cylinder for Height Adjustment
20	Panel	The Conveyor comes with a Fixed Main Panel on Rear Side and Front Side Only; Operating Panel with Emergency Stopper Sensor Bar, LED Lighting, Totally Consoled Wiring.
21	Painting	INTERNAL : High corrosion resistant Epoxy paint of required DFT
22	Belt Motor	3 HP, 1440 RPM, SEW mkae
23	Motor Make	SEW make
24	Gear Box	SEW make
25	Gear Make	SEW make
26	Motor	1.5 HP, 1440 RPM,
27	Motor Make	SEW make
28	Gear Box	SEW make
29	Gear Make	SEW make

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd