NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Omega Corporation
1006-B, Lokmat Bhawan,
Wardha Road, Nagpur-440012

Project, Location : Nagpur

Date : 26.11.2020
Quote NO : SQT.20.21.2851
Kind Attn : Vikesh Uike
Email Id : purchase@omegacorporation.co.in
Contact No: 7122437051

Subject : Quotation for Self Propelled Scissor lift.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Self-Propelled Scissor Lift**	760 mm	2160 mm	2	1,602,000	3,204,000	15,000	30,000
	Total			**2**		**3,204,000**		**30,000**
2	P&F Charges			3%		96,120		
	Total Without Taxes					3,300,120		30,000
	GST Extra @ 18%			18%		594,021.60		5,400
	Total With Taxes					**3,894,142**		**35,400**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Self - Propelled Scissor Lift

Sr .No.	Specification	Telescopic Sliding Gate
1	Load capacity	230 Kgs
2	Load capacity (on extension)	100 Kgs
3	Max working height	7800 mm
4	Max platform height	5800 mm
5	Max workers number	02 NOS
6	Overall length	1850 mm
7	Overall width	760 mm
8	Overall height	2160 mm
9	Platform size (L x W)	1670 mm X 740 mm
10	Platform extension	900 mm
11	Ground clearance	90 mm
12	Wheelbase	1360 mm
13	Turning radius	1.64%
14	Lift/drive Motor	24 v / 3.3 kw
15	Travel speed (stowed)	3 Km/h
16	Travel speed (raised)	1 Km/h
17	Raise / lower time	18/22 Sec
18	Power Source	4*6/210 v/Ah
19	Charger	24/30 V/A
20	Credibility	25%
21	Max working slope	1.5/3 Degree
22	Tyre Size	305*100 Diameter
23	Weight	1450 Kgs

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Sneha Bharane on 8551035333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd