NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Kate Food Industries Pvt. Ltd
Pune

Date : 01.09.2021
Quote NO : **MHE_21.22.0026R**
Kind Attn : Mr.Parvez khan
Email Id : p.khan1115@gmail.com
Contact No: 9977705221

Project Name & Location: Kate Food Industries Pvt. Ltd., Pune

Subject : Quotation for Inclined Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr. No.	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Inclined Belt Conveyor**	**1**	**2,75,500**	**2,75,500**	**10,000**	**10,000**
		Total		**2,75,500**		**10,000**
	P&F Charges	3%		**8,265**		
	Total Without Taxes			**2,83,765**		**10,000**
2	GST Charges @ 18%					**Extra At Actual**
3	Transportation Charges					**Extra At Actual**
4	Insurance					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

	Inclined Conveyor Legth 3.2mtr	
Sr. No.	**Parameters**	**Specification**
1	Product	Potato Chips
2	Conveyor capacity	10 Kg/min
3	Speed of conveyor	25mtr per min
4	Conveyor infeed height	200 mm
5	Conveyor outfeed height	1200 mm
6	Conveyor belt width	500 mm
7	Roller	SS-304
8	Non -contact parts	SS-304
9	contact parts	SS-304
10	Foot/Caster wheel	Spectra plast/ equivalent
11	Roller	Nihva make
12	Finish	Matt buffed
13	Conveyor height adjustment	Through foot 50 +/- mm
14	Belt	PU Food grade belt
15	Gear motor	Bonfiglioli
16	Speed control	VFD Delta make

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd