Sales Quotation

Quotation No - SQT/19-20/1807 **Date : 15/07/2019**

LM Wind Power
Dabaspet
Bangalore
Karnataka, India

Kind Attn: Mr. Prakash
Email: prakasha@lmwindpower.com
Contact No: 9886811532

Project Name:

Subject : Quotation for High speed Door RR300+ Alu .

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Unit Rate INR	Total Rate INR
A	**Albany Make(Rapid Roll Up Door RR 300 + AL)** **(100% Imported with all components – made in Germany)** 				
Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				
1	**Size: (W) 1690 mm X (H) 2280 mm** **(Supply + Installation)**	1	No.	575,000	**575,000**
2	**Size: (W) 1810 mm X (H) 2300 mm** **(Supply + Installation)**	1	No.	581,000	**581,000**
3	**Size: (W) 1790 mm X (H) 2300 mm** **(Supply + Installation)**	1	No.	580,000	**580,000**
4	**Size: (W) 3010 mm X (H) 3200 mm** **(Supply + Installation)**	1	No.	620,000	**620,000**

GST Pune : 27AAECN0437H1ZM	**Total**	**2,356,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities & the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	: Ex. Works Pune
2	**P & F Charges**	: 3% @ supply value
3	**Freight Notes**	: Extra as applicable + Taxes
4	**Delivery**	: 10 -11 weeks for HSD from the date of receipt of confirmed purchase order, Advance Payment, Drawing approva
5	**Payment**	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch
6	**Insurance**	: Extra As applicable
7	**Tax**	: GST Extra @ 18%
8	**Validity**	: Validity of Offer is 15 days from the date of quotation
9	**Warranty**	: 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on 8551096333. for any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd