NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Sales Quotation

Date : 06.02.2020
Quote NO : SQT.19.20.2345R1
Kind Attn : Mr. Bhaskar Reddy
Email Id : BHASKAR.REDDY@shapoorji.com
Contact No: 22 4892 8608

Shapoorji Pallonji And Company Private Limited
Mumbai

Project Name & Location: Flipkart: Kolkatta

Subject : Quotation for Dock Leveler, Rolling Shutter, Dock Shelter

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	UOM	Supply Charges in INR		Installation Charges	
		Clear Width (mm)	Clear Length (mm)			Unit Price	Total Amount	Unit Price	Total Amount
1	**Dock Leveler Capacity 6 Ton**	2000	2985	126	No	1,70,000	2,14,20,000	12,000	15,12,000
2	**Motorised Rolling Shutter**			1182	Sq M	5,500	65,01,000	800	9,45,600
3	**Dock Shelter**	3200	3400	126	No	56,000	70,56,000	7,500	9,45,000
			Total				**3,49,77,000**		**34,02,600**
			P&F Charges				**NIL**		
			Total Without Taxes				**3,49,77,000**		**34,02,600**
			GST Extra @ 18%	18%			62,95,860		6,12,468
			Total With Taxes				**4,12,72,860**		**40,15,068**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler

Sr. No	Description	Specifications For 6 Ton
1	Required Capacity	6 Ton
2	Hydraulic Power pack	1 HP, 3PH
3	Control Panel	4 Push Button operated
4	Deck operation	By push button Deck UP & Deck Down
5	Lip operation	By push button Deck UP & Deck Down
6	Loading platform height from road Level	4 feet (1200 mm)
7	Travel above from Dock level height	350 mm
8	Travel below from Dock level height	200 mm
9	Deck platform size	2000mm (W) x 2985mm (L)
10	Lip sizes	400 mm
11	Clear Pit dimensions	2040mm (W) x 2985mm (L) x 485mm (H)
12	Drive type	Direct by electric Motor
13	Power Consumption	0.75 kw Motor
14	Degree of protection for motor	IP 55
15	Motor RPM	1410 rpm
16	Pump design flow	1.8 LPM
17	Pump pressure	200 bar
18	Safety valve set pressure	90 bar
19	Pump type	Gear
20	In built safety valve	Yes
21	Volume of oil receiver	8 Ltr
22	No of Deck Cylinders	2 Nos
23	Deck Plate Thickness	8 mm Chequered Plate
24	No of Lip Cylinders	1 No
25	Lip Plate	16 mm Thick Plate
26	Dock Bumpers	1 Pair included

Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with Mild Steel of thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.0mm thick MS steel
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface finish	PU paint or Powder coated
12	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong

3 Dock Shelter

Sr. No	Description	Specification
1	Size	(W) 3200 mm x (H) 3400 mm
2	Quantity	126 Nos
3	Normal Width x Normal Height	(W) 3200 mm x (H) 3400 mm
4	Normal Depth	600 mm
5	Top Curtain	1000 mm
6	Side Curtain	600 mm
7	Curtain Colour	Black
8	Top and Side curtain	Double Layer High Quality Polyester
9	Thickness	3.0mm
10	Flammability all curtain	DIN 75200
11	Frame Material	Aluminum

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
3	Any civil / masonry/structural work required	In Client Scope
4	All structure support required	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
6	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 5 - 6 weeks for Dock Leveler & Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 20% Advance along with Confirmed Purchase Order against ABG, 70% against readiness of material & Balance 10% after Installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333