NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Nuclear Fuel Complex
Hyderabad-62

Date : 07.09.2019
Quote NO : SQT.19.20.0778R1
Kind Attn : Mr. Shashank Reddy A
Email Id : shashank@nfc.gov.in
Contact No: 040-27183419

Subject : Quotation for High Speed Door HS9020GAT Clean Room Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Albany Make Rapid Roll Up Door HS9020GAT	1000	2200	1	668,000	668,000	20,000	20,000
2	Albany Make Rapid Roll Up Door HS9020GAT	1500	2200	1	678,000	678,000	20,000	20,000
3	Albany Make Rapid Roll Up Door HS9020GAT	2300	3300	1	748,000	748,000	20,000	20,000
			Total			**2,094,000**		**20,000**
4	P&F Charges			3%		**62,820**		
	Total Without Taxes					**2,156,820**		
	GST Extra @ 18%			18%		388,228		3,600
	Total With Taxes					**2,545,048**		**3,600**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY - Albany Make HS9020GAT



Sr. No	Description	Specifications
1	Door Type	The HS9020GAT is a compact, airtight door with integrated motor for inside environments, type clean room
2	Door Construction	Door Constrcution in Stainless Steel 304
2	Sealing	Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss.
3	Opening & Closing Speed	Opening: up to 1.2 m/s, Closing: 0.5 m/s
4	Safety features:	• Photocells in side columns, • Flexible door curtain without ridged parts • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function.
5	Vision Window	Single row with 400 mm Height
6	Wind load resistance	Class 1 (300 Pa (N/m^2)) maximum wind load while closing 50 Pa (N/m^2)
7	Water penetration	Class 2 (50 Pa (N/m^2)
8	Air permeability	• Class 3 - Over Pressure • Class 1 - Under Pressure
9	Thermal transmittance	6,02 W/(m^2K)
10	Lifetime expectations	1,000,000 cycles

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Mallikarjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd