NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon
Bungalow No. 3, Liberty Society Phase-I, North Main Road
Koregaon Park, Pune 411 001

Date : 10.11.2020
Quote NO : SQT.20.21.2813
Kind Attn : Mr. Nagesh Jeure
Email Id : njeure@suroj.in
Contact No: 7709757563

Project Name & Location: BKT, Aurangabad

Subject : Quotation for Fire Rated Motorised Rolling Shutter and MS Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Motorised Rolling Shutter**	4000	4000	6	250,449	1,502,694	15,000	90,000
2	**Fire Rated Motorised Rolling Shutter**	3400	1710	1	177,212	177,212	15,000	15,000
3	**MS Motorised Rolling Shutter**	4000	4000	13	103,000	1,339,000	15,000	195,000
4	**MS Motorised Rolling Shutter**	3000	4000	2	102,000	204,000	15,000	30,000
4	**PVC Strip Curtain**	4000	2200	8	24,000	192,000	5,000	40,000
				Total Value		**3,414,906**		**370,000**
				P&F Charges	3%	102,447		
				Total Without Taxes		**3,517,353**		**370,000**
				GST Extra @ 18%	18%	633,124		66,600
				Total With Taxes		**4,150,477**		**436,600**
				Total (Supply + Installtion) with Taxes				**4,587,077**
4				Transportation Charges		**Extra at Actual**		
5				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
6	**Standard RAL colors:**	RAL 9002

Motorised Rolling Shutter

Sr .No.	Specification	MS Motorised Rolling Shutter
1	**Description**	MS Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement
14	**3 Station Push Button**	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 9-10 weeks for Fire rated shutters from the date of confirmed purchase order, Advance Payment & Drawing approval.
4-5 weeks for MS Motorised Rolling Shutters from the date of confirmed PO, Advance Payment & Drawing Approval

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 85510198333.**

With Best Regards
Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd