NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Kislay Veggi Farm Pvt Ltd
Bangalore

Date : 16.08.2021
Quote NO : **MHE_21.22.0033R1**
Kind Attn : Mr. Ramashish Baranwal
Email Id : ramashishb@kislay.in
Contact No: 9740644404

Project Name & Location: Kislay Veggi Farm Pvt Ltd, Nagpur

Subject : Quotation for Trcuk Loading-Unloading Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr. No.	Description	Qty	Supply Charges in INR		Installation Charges in INR for Nagpur Location	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option-1	**Loading conveyor with free roller conveyor (Cantilever 1.5mtr)**	**1**	**3,68,000**	**3,68,000**		
Option-2	**Loading conveyor with belt conveyor (Cantilever 1.5mtr)**	**1**	**3,98,250**	**3,98,250**	**30,000**	**30,000**
3	**Flat Belt Conveyor 8mtr length**	**3**	**2,38,000**	**7,14,000**		
		Total		**14,80,250**		**30,000**
	P&F Charges	3%		**44,408**		
	Total Without Taxes			**15,24,658**		**30,000**
	GST Extra @ 18%	18%		**2,74,438**		**5,400**
	Total With Taxes			**17,99,096**		**35,400**
3	Transportation Charges					**Extra At Actual**
4	Insurance					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MS Belt conveyor 8 mtr

Sr. No.	Parameters	Specification
1	Product	Bags
2	Product sizes	Please specify
3	Product weight	Please specify
4	Speed of conveyor	20 bag/min
5	Conveyor infeed height	900 mm
6	Conveyor outfeed height	900 mm
7	Conveyor belt width	750 mm
8	Conveyor belt length	8000 mm
9	Roller	MS
10	Non -contact parts	MS
11	contact parts	MS
12	Caster wheel	Spectra plast/ equivalent
13	Roller	NIHVA Make
14	Finish	Powder coated
15	Belt	PVC belt
16	Gear motor	Bonfiglioli

MS Inclined Belt Conveyor (Cantilever 1.5mtr)

Sr. No.	Parameters	Specification
1	Product	Bags
2	Product sizes	Please specify
3	Product weight	Please specify
4	Speed of conveyor	20 bag/min
5	Conveyor infeed height	900 mm
6	Conveyor outfeed height	1850 to 3600 mm
7	Conveyor belt width	750 mm
8	Conveyor belt length	As per layout
9	Roller	MS
10	Non -contact parts	MS
11	contact parts	MS
12	Caster wheel	Spectra plast/ equivalent
13	Roller	NIHVA Make
14	Finish	Powder coated
15	Belt	PVC belt
16	Gear motor	Bonfiglioli

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd