NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Crane ChemPharma & Energy
E7/ E8- 2, Old MIDC, Satara, India, PIN Code- 415 004

Project, Location : Satara

Date : 08.07.2021
Quote NO : SQT.20.21.2878R2
Kind Attn : Nagaraju Peruvala
Email Id : NPeruvala@cranecpe.com
Contact No: 9130082427

Subject : Quotation for ASSA ABLOY Dock Leveler and Manual / Automatic Restraint System.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Dock Leveler - Swing Dock**	2000	2500	2	420,000	840,000	Inclusive	
2	**Manual Restraint System H400**			2	561,000	1,122,000	Inclusive	
3	**Automatic Restraint System**			2	1,205,000	2,410,000	Inclusive	
4	**Wheel Guide**	1 Set		2	5,000	10,000	Inclusive	
	Total			**8**		**4,382,000**		-
5	P&F Charges			3%		131,460		
	Total Without Taxes					4,513,460		-
	GST Extra @ 18%			18%		812,423		-
	Total With Taxes					**5,325,883**		**-**
6	Transportation Charges					In NIHVA Scope		
7	Unloading Charges @ Site					In NIHVA Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Dock Leveler - Swing Dock

ASSA ABLOY DL6010S swingdock is the standard solution in general industry applications. Its swing lip safely bridges the gap between the ramp and the vehicle bed.

Description	Specification
Nominal Width	2000 mm
Nominal Length	2500 mm
Leveller Height	600 mm
Load Capacity	60 kN
Leveller Surface Treatment	RAL 5010 (Gentian Blue)
Leveller Paintclass	80 µm
Lip Material	STEEL
Lip Length	400 mm
Lip Bevellment	100 mm
Tearplate Thickness	6 mm
Control Box	950 L
Control System	Mains Switch

ASSA ABLOY Manual Restraint System

Description	Specification
Power supply	230V 1-phase
Power	10 Amps
Control	24V DC
Overall length, width and height	2030 mm x 750 x 750 mm
Weight	180 kg
Wheel blockage height	Approx. 400 - 450 mm
Control Box	
Signal green to indicate leveler or sectional door is released. The truck is docked and blocked, the loading operation can begin	
Signal red to indicate leveler or sectional is blocked and the truck is not in place.	
Beeper, adjustable in noise level.	
Key switch for service	
Signal red when the key switch for service is activated	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Auomatic Restraint System

Description	Specification
Restraint force:	200kN
Standard cable length	Motor cable 15 m, Sectional door sensor cable 2,5 m, Dock leveler sensor cable 15 m
Traffic light	Integrated on the carriage
Interlocking	Sensor for sectional door. Sensor for dock leveler
Outside LED light	Has a brightness sensor and lights up when it is dark
Override key switch	Disconnects the interlocking functions
Winter mode switch	The hydraulic unit will run in a closed circuit for one minute, every four hours
Working range of the restraint system	The rear position of the ASSA ABLOY DE6190AR automatic restraint is 100 mm in front of the buffer to allow the operation of trucks with tail lifts. In this position, the distance from the buffer to the rear wheel must be min. 670 mm (570 mm from the wheel detection arm plus 100 mm from the buffer).
Dimensions of suitable wheels	Dimensions of suitable wheels Diameter between 760 and 1.200 mm
Free space in front of the wheel (for the blocking arm)	W250mm and H370mm
Power supply	380 V Tri+Terre
Power	7 Amps
Control	24 V DC
MOELLER automaton	EASY 721-DC-TC
Stabilized power supply	24 V DC protected (fuses not needed)
Withdrawable relays	YES – Facilitates maintenance
Cabling with connectors	YES – Facilitates maintenance
Door position sensor	YES (serial) – Reflex Sick sensor (interlocking ED 6059)
"NO" contact motorized door blockage	YES (serial) – Feedback to terminal block (interlocking ED 6059)
"NO" contact hydraulic dock blockage	YES (serial) – Feedback to terminal block (interlocking ED 6059)
Blocking arm position sensor	Inductive sensor with control indicator light NBN8-12GM50-E2-V1
Wheel detection sensor	Inductive sensor with control indicator light NBN8-12GM50-E2-V1
Automatic safety lighting	YES (serial) – 2 LED lights 4 W with adjustable dusk light
Signalization LED lights	YES (serial) – Red and green LED strips on the carriage
Interior indicator light LED signalization	YES (serial)
Beeper alarm	YES (serial) - Adjustable
Maintenance contact key	YES (serial) with control indicator light
Summer/winter function	YES (serial)
Automatic return function (if there is no vehicle)	YES (serial) – Avoids wrong maneuvers from blocking the dock
Releasing security in case the vehicle is not braked	YES (serial) – Very important if the dock is on a slant
Hydraulic unit	Motor 1.1 Kw TX 905-1500 rpm 220/380 Tri, adjusted at 60 bars
Hydraulic pump	9,8 cc MHYDE 3434 tank 12 liters
Solenoid valves and coils withcontrol indicator LED lights	2 solenoid valves NG6 VNK 4 coils 24 Volts DC2 anti-reverse steered in A-B 22S6-50 NG6 VNK
Plugs	Sets in 3/8
Hoses	SAE 100 3/8 service pressure 330 bars
Oil	HM46 SAE 20
Overall length, width, and height of the restraint system	4500 mm x 750 mm x 500 mm
Weight	800 kg
Wheel blockage height	370 mm

The working range of the system depends on the size of the wheel set of the trucks.		
Wheel set diameter	760mm	1.200mm
Min. distance to buffer from the center of the	1.150mm	1.040mm
Max. distance to buffer from the center of the	4.030mm	3.900mm
Working range	2.88	2.86

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.
2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune
Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd