NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ACR PROJECT CONSULTANTS PVT LTD
103, Sanskruti Vijay Apts
Prabhat Road Lane No. 9/3, 39/35, ERANDAVANA,
PUNE - 411004

Date : 04.12.2019
Quote NO : SQT.19.20.2244R
Kind Attn : Mr. Mayur Ghule
Email Id : acrprojects@acrconsultants.net
Contact No: **+ 91 20 25464327**

Project Name & Location:

Subject : Quotation for Sliding Gate and Wicket Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MOTORISED SINGLE LEAF SLIDING GATE**	8500	2000	2	305,000	610,000	15,000	30,000
2	**MOTORISED SINGLE LEAF SLIDING GATE**	5200	2000	1	258,000	258,000	15,000	15,000
3	**MANUAL WICKET GATE**	2100	2000	1	35,000	35,000	5,000	5,000
			Total			**903,000**		**50,000**
	P&F Charges			3%		**Nil**		
	Total Without Taxes					**903,000**		**50,000**
	GST Extra @ 18%			18%		162,540		9,000
	Total With Taxes					**1,065,540**		**59,000**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	**Motorized Sliding Gate**
Clear Opening gate dimension	1. (W) 8500 x (H) 2000…in mm 2.(W) 5200 x (H) 2000…in mm
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	72 x 72 x 3.2mm MS SQ. TUBE
Internal Vertical Tube Sizes	30 x 30 x 2.6mm MS SQ. TUBE
Gap Between Tubes	350 mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd