NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PR Arch Solutions

Date : 11.06.2020
Quote NO : SQT/19-20/26003
Kind Attn : Mr.Jignesh Shah
Email Id : prt_hardware@yahoo.co.in
Contact No: 9925047249

Subject : Quotation for Sectional Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option -1							
1	**Fully glazed Sectional Door**	4250	2750	1	328,000	328,000	20,000	20,000
	Option -2							
1	**Sectional Door**	4250	2750	1	271,000	271,000	20,000	20,000
				Total		**328,000**		**20,000**
2	P&F Charges			3%				
	Total Without Taxes							
	GST Extra @ 18%			18%		-		-
	Total With Taxes					**-**		**-**
3	Transportation Charges					In Client Scope		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification



Sr .No.	Specification	Fully glazed overhead Sectional Door -Crawford - NIHVA Assaabloy
1	**Door type**	OH1042FG
2	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000 certified
3	**Frame thickness**	44 mm
4	**designed to be used**	maximum light, exposure, or vision.
5	**Panel Thickness**	42mm
6	**Panel colour**	all RAL colours available.
7	**Thermal transmittance, EN 12428**	6 W/m2K
8	**Water penetration, EN 12425**	class 3
9	**Air permeability, EN 12426**	class 3



Sr .No.	Specification	Sectional - Crawford - NIHVA Assaabloy
1	**Door type**	1042P
3	**Opening Direction**	90 Degree
5	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000 certified
6	**Opening/Closing Speed**	0.25 m/s
7	**Door Material**	GI Steel with PUF inside
8	**Panel Thickness**	42mm
9	**Panel colour**	RAL 9002 Powder coated
10	**External surface of the panel**	diamond grid design with a glossy finish at the section joints.
11	**inside surface of the panel**	Monolithic surface on the inside of the door
12	**Broken cold bridge**	Section joints with broken cold bridges

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain on 855192333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd