NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TASTY BITE EATABLES LTD.
490,Village Bhandgaon,
Takuka Daund,
Distict - Pune, 412214
Maharastra

Date : 25.01.2020
Quote NO : SQT.19.20.2352R
Kind Attn : Mr. Sndeep Bhansali
Email Id : Sandeep.Bhansali@effem.com
Contact No :

Project Name & Location: Pune.

Subject : Quotation for Rolling Shutter, High Speed Door , Sectional Door and Dock Leveller.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GI Motorised Rolling Shutter + Structure**	4000	5000	1	258,000	258,000	20,000	20,000
2	**GI Motorised Rolling Shutter + Structure**	3700	4000	1	232,000	232,000	20,000	20,000
3	**GI Motorised Rolling Shutter + Structure**	4000	4500	2	248,000	496,000	20,000	40,000
4	**Double Wall Motorised Rolling Shutter + Structure**	5000	6000	1	547,000	547,000	20,000	20,000
5	**High Speed Door HS9020G + Structure**	2800	2760	1	539,000	539,000	20,000	20,000
6	**High Speed Door HS9020G + Structure**	2800	3000	1	549,000	549,000	20,000	20,000
7	**Sectional Door + Structure**	2600	3000	2	335,000	670,000	20,000	40,000
8	**Nihva Make Dock Leveller + Structure**	3400	3400	2	95,000	190,000	20,000	40,000
9	**Dock Shelter**	3400	3400	2	95,000	190,000	20,000	40,000
10	**Dock House (NIHVA Make)**	3450	3600	2	290,000	580,000	20,000	40,000
				Total		**3,671,000**		**260,000**
11			P&F Charges	3%		**110,130**		
			Total Without Taxes			**3,781,130**		**260,000**
			GST Extra @ 18%	18%		680,603		46,800
			Total With Taxes			**4,461,733**		**306,800**
12			Transportation Charges			**In Client Scope**		
13			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1.Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection

2.Rolling Shutter

Sr .No.	Specification	Double Wall Rolling Shutter
1	**GI Slat**	1.0 mm Thick .
2	**Profile**	Curved Type Profile with heavy duty Shaft
3	**Guide**	2.5 mm Thick MS Guide
4	**Hood Cover & Motor Cover**	0.9 mm Thick GI material .
5	**Drive**	Direct Drive
6	**Curtain Profile**	Curved

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

3 .High Speed Door




HS9020G



SIDE GUIDES



Safety Facilities



Sr. No	Description	Specifications
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	**Wind load resistance**	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	**Air permeability**	Class 1 (24 m³/m²/h at 50 Pa)
8	**Water penetration**	Class 2 (50 Pa (N/m²))
9	**Thermal transmittance**	6,02 W/(m²K)
10	**Lifetime expectations**	1.000.000 cycles
11	**Temperature working range**	5 °C to +40 °C
12	**Vision window**	Horizontal one row of height 400 mm at eye level

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

4 .Sectional Door


Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Door type**	1042P	
2	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000	
3	**Opening/Closing Speed**	0.25 m/s	
4	**Door Material**	GI Steel with PUF inside	
5	**Panel Thickness**	42mm	
6	**Panel colour**	RAL 9002 Powder coated	
7	**External surface of the panel**	diamond grid design with a glossy finish at the section	
8	**inside surface of the panel**	Monolithic surface on the inside of the door	
9	**Broken cold bridge**	Section joints with broken cold bridges	
10	**Door sealent**	All door sealants made of EPDM rubber.	
11	**All Panel height**	All panels should be 545mm high	
12	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
13	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
14	**Steel component Material**	All steel components to be electro galvanized	
15	**Hinge Material**	Glass fibre reinforced Polyamide	
16	**Panel Thickness**	42 mm	
17	**Spring Material surface finish**	Powder coated	
18	**Water Penetration**	EN 12425	class 3
19	**Air Permealibity**	EN12426	class 2
20	**Wind Load**	EN21424	class 3
21	**Thermal Transittance**	EN 12428 1.10W /m2K	
22	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
23	**Door saftey device 1**	Doors equiped with spring break device	
24	**Interlocking with High Speed Door**	Included	
25	**Door saftey device 2**	Door equiped with pneumatic safety edge	
26	**Door saftey 3**	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

5 .Nihva Make Dock Leveller





Description	Specifications
Capacity	3.5 Ton
Dock operation mode	AC power pack hydraulically operated
Lip operation mode	Hydraulic
Operation control	Through panel
Loading platform height from road	1250mm
Travel above & below dock level	(+) 300 / (-) 250 mm
Platform Size (W x L)	2200 mm x 2500 mm
Lip size (W x L)	2200 x 400 mm
Shut Height	480 mm
Overall length	2200mm x 2500mm + Lip Length (400mm)
Maximum slope can be achieved	10%
Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 2550 mm x (D)485 mm
Hydraulic power pack	Standard
Driver type	Direct by electric Motor
Motor Ratings	1 H.P
Pump design flow	2.5 LPM
Pump pressure	120 bar Operating 200 bar Max.
Safety valve set pressure	120 Kg/cm²
Pump Type	Gear
Volume of oil receiver	7 Lit
No Of Deck cylinder	2 No
Lip Cylinder	1 No
Structure	Included
Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 -10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333 .**

With Best Regards
Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd