NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Indamer
Mumbai Operation Gate No. 8, Militry Camp,
Kalina, Santacruz (E), Mumbai - 400 029

Project, Location :

Date : 19.1.2021
Quote NO : SQT.20.21.2943R
Kind Attn : Rohan Dhumal
Email Id : rohand@aarindamertechnics.com
Contact No: 9579622491

Subject : Quotation for Bollards

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Diameter (mm)	Shaft Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	(Option-I)							
1	Pillar B 275/800.10C - K4 Equivalent Crash rated (High Security automatic Hydraulic bollard)	275	800	16	710,000	11,360,000	25,000	400,000
2	PERSEO CBE 230.P SD: Control unit			4	90,000	360,000		-
3	Dual Channel Metal Detector			4	45,000	180,000		-
	Total			**24**		**11,900,000**		**400,000**
4	P&F Charges			3%		357,000		
	Total Without Taxes					12,257,000		400,000
	GST Extra @ 18%			18%		2,206,260.00		72,000
	Total With Taxes					**14,463,260**		**472,000**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NOTE :	**Every Bollards needs Civil Pits.** **Civil Pits work in Clients Scope.**





Automatic hydraulic bollard for high security protection

Indipendent hydraulic pump for each bollard, access for simplifi ed servicing, anti-tampering sensor (optional)
• Break-in resistance: 667 000 J (*)
• Impact resistance: 40 000 J
• Work time: rise time: ≤ 7.0 s; lowering time: ~ 4.0 s
• Max operating frequency: up to 2 000 op./day
• MCBF: 3 000 000 cycles
• Sensors for bollard positions: fully up
• Obstacle sensing, confi gurable (with/without movement inversion)
• Bollard top cover, cast iron. LED lights and buzzer
• Interfaces for remote control (RS485 - TCP/IP, optional)
• In case of power loss:
Standard version: bollard goes down, electrical emergency unit for maintaining the bollard up (optional).
Security version: bollard stays up, bollard can be lowered by means of a mechanical key accessible through the ground fl ange.

TECHNICAL-ENVIRONMENTAL MAIN FEATURES	
Tube height	Ø273 x h. 800 mm (± 3 mm) x th. 10 mm, steel Fe 360 (S 235 JR)-Optional, AISI304 or AISI316
Buried structure	Ø354 x h. 1 060 mm
Foundation	Concrete
Excavation pit	1 200 x 1 200 x 1 400 mm
Break-in resistance	667 000 J
Impact resistance	40 000 J
Tube treatment	Cataphoresis and coating RAL7015 standard, other colours on request
Passive visibility	Refl ective fi lm H=100 mm Customizable (optional)
Flange	Cast iron, cataphoresis black
Top cover	Cast iron, cataphoresis black
Actuator	Hydraulic, biodegradable oil
Power	230 Vac ±10%, 50-60 Hz
Working time	rise time: ≤ 7.0 s (50 Hz); lowering time: ~ 4.0 s
Operating humidity	up to 100%
IP grade	IP67
Manual operation	During power failure: - Standard version: bollard goes down. - Security version: bollard stays up, bollard can be lowered by means of a mechanical key accessible through the ground fl ange.
Net weight	189 kg
Gross weight	197 kg

Sr No	Description	Specification
1	Control unit	PERSEO CBE
2	Power	1-phase 230 Vac ±10%, 50-60 Hz (115 Vac with optional adapter)
3	IP grade	IP54
4	Operating humidity	up to 95%, non condensing
5	Bollard driven	Max. 4 for each control unit. Parallel control wiring possible for driving many groups of bollards.
6	Power consumption, max	0.50 kW for each bollard
7	Power consumption, idle	28 W
8	Signalling	On the top with high intensity LEDs, and buzzer
9	Sensors	Open passage/bollard down, closed passage/bollard up, Overpressure/Obstacle, antitampering switch (optional)
10	Local/Remote control	Digital inputs Radio remote control (receiver included, transmitter optional) RS485, TCP/IP (optional)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd