To,
Mr. Vijay Tarak,
M/s Nihva technologies pvt. Ltd,
Pune

Ref.: SHPL/SP/1712884/R1

Date: 02.04.2017

Project: Phase-I

Dear Sir,

Please find below our offer for Hormann Industrial Doors.

The advanced features and advantages of the Hörmann range of products are listed below for your kind perusal .

Specifications:

Hormann Motorized Insulated rolling shutter Decotherm® S SB (smaller sizes):

Insulated Rolling Shutters	
Features	**Benefits**
Thermal Insulation	Shutter infill of 20mm PU rigid foam ensuring excellent thermal insulation
Acoustic	Double skin rolling shutters ensures noise reduction from outside up to 22 db.
Side guide Protection	Black plastic strips on the edge of the side guides protect against abrasion and ensure longevity of shutters.
Closing edge safety device(only for motorized)	Sensor controlled safety devices to monitor the bottom edge of the door. Instant stoppage and reversing on encountering any obstruction while closing.
Sealing	Rubber seals are provided to reduce friction and sound, thereby ensuring a smooth door travel
Accessories(optional)	Vision panels for better visibility and light can be provided at extra cost.

Door Curtain:

- Decotherm S

Support Brackets:

- Galvanized steel

Space requirement (in mm):

- Head room(S) =675
- Min. fitting depth for operator & support brackets(ET)=450 (Space required for removal of cover is 2 times of cover)
- Side space requirement(PS) =210

Minimum requirements for the building structure:

- Concrete =140mm (Min strength M10)
- Steel=5mm (5mm Thickness)
- Brick work=240mm (Min strength 100 Kg/cm²)

Side guides:

- FS 160 A: moulded aluminum guide rails With guide channel, black plastic runner

Bottom Profile:

- Extruded aluminum
- Double skinned

Seals:

- Lintel seal, Bottom seal made of EPDM profile.

Fixing material:

- Tested and approved for steel, concrete, brickwork

Counterbalance:

- Tension springs

Wind Load:

- Decotherm S standard wind load class 3 (EN 12424)

For automated door operation:

Operator:

- Shaft operator
- Ready-to-fit shaft operator
- Power input- 1- phase current 0.25 kW
- Protection category IP 65 (jet-water protected).
- Number of cycles : 10cycles/hour

Control:

- Integrated microprocessor control along with operator
- Adjustable force limit
- Connection cable with CEE male plug in protection category IP 44

SHPL scope – standard supplied along with Door:

- 16A, 3 pin, industrial male socket with 1Mtr cable alongwith controller

Client scope – To be provided at site for commissioning:

- 16A, 3 pin, industrial Female socket with in 1Mtr from controller



Price:

Price summary-Supply								
Sl.No.	**HSN CODE**	**Supply Description**	**Qty in No's**	**Basic Price / Unit (INR)**	**Basic Amount (INR)**	**IGST Rate (%)**	**IGST Amount (INR)**	**Total Value (INR)**
1	**7308**	Hormann RS Decotherm® S SB 3000x3000mm	2	1,30,000	2,60,000	18%	46,800	3,06,800
2	**7308**	Hormann RS Decotherm® S SB 3000x3500mm	2	1,35,000	2,70,000	18%	48,600	3,18,600
Supply cost			**4**		**5,30,000**		**95,400**	**6,25,400**
Transportation @ client scope								
Total cost (supply)			**4**		**5,30,000**		**95,400**	**6,25,400**
Total in words: INR Six lakhs twenty five thousand four hundred only.								

Price summary-Installation								
Sl.No.	**SAC CODE**	**Installation Description**	**Qty in No's**	**Basic Price / Unit (INR)**	**Basic Amount (INR)**	**GST Rate (%)**	**GST Amount (INR)**	**Total Value (INR)**
1	**998731**	Hormann RS Decotherm® S SB	4	20,000	80,000	18%	14,400	94,400
Total installation cost			**4**		**80,000**		**14,400**	**94,400**
Total in words: INR Ninty four thousand only.								

Terms and conditions:

The price quoted above includes GST as applicable. Any change at the time of dispatch will be extra at actual to client account.

Terms of payment:

50% advance payment along with purchase order and 50% balance against Proforma invoice prior to dispatch.

Dispatch: Approx. 4-5 weeks from the date of receipt of all technical clarifications and payment for Rolling shutters

GST: Included @ 18% or as applicable at time of dispatch

Freight : Transportation shall be under client scope unless otherwise specified in the Quote or Purchase order issued against this quotation.

Insurance : Transportation is your scope(Client's scope) OR if the material to be sent on ``TO PAY'' basis, insurance during the transit and at site shall be your responsibility.

Warranty: 12 months from date of handing over or 13 months from the date of delivery, whichever is earlier. Electrical components will not be covered under warranty.

Cancellation of order:

Since, this is a customised order, in the event of the order being cancelled by you after payment of advance, the advance paid shall be forfeited without any notice and shall not be refunded. Any alterations to the specification given shall be intimated within one week from the date of Order or prior to the commencement of the production of the door , which ever is earlier.

Acceptance of Purchase Order: The order is commercially clear on receipt of the following information
a) our acceptance and confirmation of all terms of the purchase order.
b) Receipt of advance though elctroinic transfer or by way of a demand draft in favour of "Shakti Hormann Private Limited" payable at Hyderabad.

Purchase order to be raised on the below address:

Shakti Hormann Pvt.Ltd.
Plot No. 20, Sripuri Colony, Karkhana,
Secunderabad. Telangana – 500 015.
Phone number:-+91 40 27840394 / 95
CIN No:-U65110TG1988PTC009207

Tin No:-36510123335
PAN no:-AADCS4024Q
GST No: 36AADCS4024Q1Z1

Bank Details: All online payments shall be made to the account details mentioned below:

Name of the Bank : HDFC BANK LIMITED.
CCA/c No : 00210310005678
RTGS / IFSC Code : HDFC000021

Force Majeure: Shall be applicable to cover events such as natural calamities, strikes, lockouts, hartals etc.,and any other conditions beyond our control.

Jurisdiction: All disputes arising under this contract shall be subject to the jurisdiction of the Secunderabad / Hyderabad courts only.

Purchase Order: All pages of the quotation, terms and conditions shall be signed and enclosed as annexure to the purchase order released by you.

Duties taxes: All duties, taxes and other Government levies quoted are as per the current rates applicable. However, the rates prevailing at the time of dispatch shall be charged.

Installation: **A separate Work Order to be released for installation.**
Installation shall commence only on receipt of payment against supplies.

(a) Payment terms : 30% advance before commencement of installation and balance 50% on mechanical installation & 20% on commissioning.

(b) Civil work and reinforcements (C-channel etc.) required in preparation of the installation, as well as the removal of existing doors or other installed products, is not included in this proposal and is in clients scope.

(c) A suitable, stable and clean electrical mains connection (**1-Phase stable for RS clean power supply without any Voltage Fluctations**) will be made available by the customer prior to our installation and is outside our scope of deliverables.

(d) Conduiting will be done by client and is out of our scope. Suitable clean power will be made available through voltage stabilizer or spike buster by the client upto the control panel of door.

(e) UPS is mandatory and shall be under client scope.

(f) Onsite storage, unloading, scaffolding, hydra or forklift is not in our scope and is to be provided by client.

(g) The installation charges are based on the assumption that the installation can be carried out in one continuous exercise. Should multiple visits be necessary or required by you, we will charge additional travel expenses charged at actual

Offer Validity: **30 days from the date of offer**

We trust this proposal meets with your approval and look forward to your order and being a part of your prestigious project .

Kindly let us know if you require any futher clarifications , we will pleased to provide the same.

From,
M/s Shakti Hörmann Pvt Ltd,
Plot No 20, Sripuri Colony,
Karkhana, Hyderabad-500 015,
Telangana, India.
Tel: +91 40 27840394/95,
Fax: +91 40 27892327.