NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SERUM INSTITUTE OF INDIA PVT LTD
Hadapsar
Pune 411028

Date : 27.11.2019
Quote NO : SQT.19.20.2198R1
Kind Attn : Mr. Sandesh Sable
Email Id : sandeshkumar.sable@seruminstitue.com
Contact No: 9930911735

Project Name & Location:

Subject : Revised Quotation for BI PARTING TWO LEAF TELESCOPIC SLIDING GATE (MOTORIZED)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**BI PARTING TWO LEAF TELESCOPIC SLIDING GATE (MOTORIZED)**	23000	2500	1	1,690,000	1,690,000	28,500	28,500
				Total		**1,690,000**		**28,500**
2	P&F Charges on Total Supply Value			NIL				
	GST Extra @ 18%			NIL	Due to SEZ			
3	Transportation Charges				**In client scope**			
4	Unloading Charges @ Site				**In client scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No.	Description	Specification
1	Gate type	BI PARTING TWO LEAF TELESCOPIC SLIDING GATE (MOTORIZED)
2	Clear Opening gate dimension in mm	23000 (W) x 2500 (H)
3	Opening Direction	Bi Parting
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm MS SQ. TUBE
6	Inner Tube	40 x 40 x 2.6 mm MS SQ. TUBE
7	Post Tube	80 x 80 x 3.2 mm MS SQ. TUBE
8	Gap Between Tubes	125mm C/C
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	European Make Motor
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light
17	Metal Rack	Zinc plated metal rack
18	Telescopic Mechanism	Inbuilt with Gate
19	Installation Checks	need to be check = space requirements + substructure + Mounting access + Access in the event of power cut

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 30% advance along with Purchase order, 60% after dispatch & 10% after completion

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd