**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Radhesham Well Pack**
Chakan, Pune

**Date :** 15.02.2021
**Quote NO :** AS_20.21.0009R2
**Kind Attn :** Mr. Vishal R Panjabi
**Email Id :** vishal312@gmail.com
**Contact No:** 9922265500

**Project Name & Location: Loading Conveyor, Pune**

**Subject : Quotation for Loading Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 1 |
| C. | General Conditions | 2 |
| D. | Terms & Conditions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Loading Conveyor -** 10feet cantilever | 1 | 3,61,000.00 | **3,61,000.00** | **NIHVA Scope** | **NIHVA Scope** |
| | **Total** | | | **3,61,000.00** | | |
| | P&F Charges | 3% | | | | **Included** |
| | **Total Without Taxes** | | | **3,61,000.00** | | |
| | GST Extra @ 18% | 18% | | **64,980.00** | | |
| | **Total With Taxes** | | | **4,25,980.00** | | |
| 2 | Transportation Charges | | | | | **NIHVA Scope** |
| 3 | Unloading Charges @ Site | | | | | **In Client Scope** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Loading Conveyor**

| Parameters | Specification |
|---|---|
| Product | Cartoon sheet |
| Product size | 1800 x 1800 x 500 |
| Product weight | 25Kg |
| Product capacity | Please specify |
| Conveyor capacity | 50Kg/min |
| Speed of Conveyor | 12mtr/min |
| Conveyor Infeed height | 700 mm |
| Conveyor Outfeed height | 900 mm |
| Contact parts | MS powder coated |
| Non-contact parts | MS powder coated |
| Gear Motor | Bonfiglioli |
| Foot | Caster Wheel |
| Belt with bottom profile | PVC green belt |
| Belt Make | Chiorino (Italy) |
| Belt width | 1000mm |
| Conveyor width | As per layout |
| Finish | Powder coated |
| Speed control through | VFD optional |

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**D) Terms & Conditions**

**Price** : Ex Works Pune.

**Delivery** : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 30% Advance along with Confirmed Purchase Order, 60% Before dispatch of material and remaining 10% after installation.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd