NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Torrent Power Ltd.

Date : 28.05.2020
Quote No : SQT.19.20.2541
Kind Attn : Mr. Hardik Prajapati
Email Id : hardikprajapati2@torrentpower.com
Contact No: 90990 08324

Project Name & Location: TCI,Kamrej.

Subject : Quotation for Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Manual Mobile Scissor lift	1200	2100	1	5,88,000	5,88,000	20,000	20,000
				Total		**5,88,000**		**20,000**
2			P&F Charges	3%		**17,640**		
			Total Without Taxes			**6,05,640**		**20,000**
			GST Extra @ 18%	18%		1,09,015		3,600
			Total With Taxes			**7,14,655**		**23,600**
3			Transportation Charges			**Extra at Actual**		
4			Unloading Charges @ Site			**Client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1 Manual Mobile Scissor lift

Description	Specifications
Capacity	300 Kgs
Platform Size	(W) 1200 mm x (L) 2100 mm
Shut Ht	1800 mm
Max ht	10000 mm
Lift Ht	8200 mm
Safety Railing	3 side fix & one side Hinged door 900 Height
Wheels	2 Nos Swivel and 2 Nos Fixed
Floor Locks	4 Nos for stability
	Fix ladder for climbing on top platform
	Safety limit switch for max ht
	Trolley moment manual push-pull (Self weight of trolley approx 2000Kg)
Color	Golden Yellow (RAL 1004)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd