**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**WANI PROJECTS & INFRA PVT LTD(HO)**
401 A, PHOENIX EAST COURT
VIMAN NAGAR PUNE :- 411014.

**Project, Location : ESR Palava**

**Date :** 25.03.2021
**Quote NO :** SQT.20.21.3108R
**Kind Attn :** Chintamani Ranbhor
**Email Id :** chintamani@wanigroup.com
**Contact No:** 9767213687

**Subject : Quotation for Rolling Shutters, Dock Leveler, Telescopic Gate, Metal Door and Fire Door.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Motorized Single Skin Rolling Shutter** | 4000 | 5000 | 4 | 172,000 | 688,000 | 20,000 | 80,000 |
| 2 | **Gear Operated Rolling Shutter** | 3000 | 3000 | 2 | 80,000 | 160,000 | 20,000 | 40,000 |
| 3 | **Dock Leveler - 5 Ton** | 2000 | 2500 | 3 | 220,000 | 660,000 | 15,000 | 45,000 |
| 4 | **Fire Door** | 1200 | 2100 | 8 | 49,000 | 392,000 | 8,000 | 64,000 |
| 5 | **Metal Door** | 1200 | 2100 | 2 | 34,000 | 68,000 | 8,000 | 16,000 |
| 6 | **Telescopic Sliding Gate** | 9000 | 1800 | 1 | 424,000 | 424,000 | 20,000 | 20,000 |
| 7 | **Telescopic Sliding Gate** | 6000 | 1800 | 1 | 392,000 | 392,000 | 20,000 | 20,000 |
| | **Total** | | | **21** | | **2,784,000** | | **285,000** |
| 8 | P&F Charges | | | 3% | | 83,520 | | |
| | **Total Without Taxes** | | | | | 2,867,520 | | 285,000 |
| | GST Extra @ 18% | | | 18% | | 516,153.60 | | 51,300 |
| | **Total With Taxes** | | | | | **3,383,674** | | **336,300** |
| 9 | Transportation Charges | | | | | Extra at atcual | | |
| 10 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Motorized Rolling Shutter**

| Sr .No. | Specification | GI Motorized Rolling Shutter |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with GI Slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 12 | **Surface finish** | PU paint or Powder coated |
| 13 | **Drive Unit & Mounting Type** | Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection |

**Gear Operated Rolling Shutter**

| Sr .No. | Specification | GI Gear Operated Rolling Shutter |
|---|---|---|
| 1 | **Description** | Gear Operated Rolling Shutter with GI slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 11 | **Surface finish** | 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer |
| 12 | **Operation** | Gear Assembly. |

**2 Hrs Fire rated Door**

| Sr. No | Description | 2 Hrs Fire rated Door |
|---|---|---|
| **1** | Description | Fire Resistant Door Single Leaf Hinge Type (2 Hour Fire Rated) 1.20 mm thick G.I Sheet cladded 46mm thick shutter with infill Material Mineral Wool (Density – 96 Kg/M3) complete with G.I. frame (Single Ribet – Frame Profile 100 x 57mm) made from 1.60mm thick G.I. Sheet & Fixing arrangements AS PER BS 476 (PART- 20 &22); IS: 3614 (Part-II) for Integrity, Stability. Paint Finish. |
| **2** | Door Size | 1200mm (W) x 2100mm (H) |
| **3** | Accessories | S.S. Ball Bearing Hinges - 04 nos |
| | | Panic Bar Exit Device for Single Leaf Door - 01 Nos |
| | | External Trim bar Panic Latch - 01 Nos |
| | | Vision Panel with Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass) |
| | | Heavy Duty Door Closer – Dorma Make TS 68 |
| | | Concealed Flush Tower Bolt - 01 Nos |

**Single Leaf Steel Door without Panic Bar**

| Sr. No | Description | Steel Door |
|---|---|---|
| **1** | Description | General Purpose Steel (HMPS) Doors Single Leaf Hinge Type 0.80 mm thick M.S. Sheet cladded 40mm thick shutter infill material as Honeycomb complete with M.S. frame (Single Rebate – 100 x 57mm) made from 1.20mm thick M.S. Sheet & Fixing arrangements. Finish – Paint Finish. |
| **2** | Door Size | 1200mm (W) x 2100mm (H) |
| **3** | Accessories | S.S. Ball Bearing Hinges - 04 nos |
| | | S.S. 'D' Type Handle - 01 Nos |
| | | Dead Lock with Cylinder - 01 Nos |
| | | Vision Panel with Non - Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass) - 01 Nos |
| | | Heavy Duty Door Closer – Dorma Make TS 68 |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Dock Leveler**

| Sr .No. | Specification | Dock Leveller |
|---|---|---|
| 1 | **Capacity** | 5 Ton |
| 2 | **Dock operation mode** | AC power pack hydraulically operated |
| 3 | **Lip operation mode** | Hydraulic |
| 4 | **Operation control** | Through panel |
| 5 | **Loading platform height from** | 1250mm |
| 6 | **Travel above & below dock level** | (+) 300 / (-) 250 mm |
| 7 | **Platform Size (W x L)** | 2000 mm x 2500 mm |
| 8 | **Lip size (W x L )** | 2000 x 400 mm |
| 9 | **Shut Height** | 480 mm |
| 10 | **Overall length** | 2000mm x 2500mm + Lip Length (400mm ) |
| 11 | **Maximum slope can be achieved** | 0.1 |
| 12 | **Clear Pit dimensions (W x L x D)** | (W) 2050mm x (L) 2550 mm x (D)485 mm |
| 13 | **Hydraulic power pack** | Standard |
| 14 | **Driver type** | Direct by electric Motor |
| 15 | **Motor Ratings** | 1 H.P |
| 16 | **Pump design flow** | 2.5 LPM |
| 17 | **Pump pressure** | 120 bar Operating 200 bar Max. |
| 18 | **Safety valve set pressure** | 120 Kg/cm² |
| 19 | **Pump Type** | Gear |
| 20 | **Volume of oil receiver** | 7 Lit |
| 21 | **No Of Deck cylinder** | 2 No |
| 22 | **Lip Cylinder** | 1 No |
| 23 | **Yellow and Black Strips for Side** | Included |
| 24 | **Dock Bumper** | Pair of Dock Bumper |
| 25 | **Dock Bumper steel Gard** | Steel Support Plates |
| 26 | **Operation** | not stopping automatic while any truck movement |

**Telescopic Sliding Gate**

| Sr .No. | Specification | Telescopic Sliding Gate |
|---|---|---|
| 1 | Door type | Motorised Three Leaf Telescopic Sliding Gate |
| 2 | Clear Opening gate dimension | (W) 9000 mm X (H) 1800 mm & (W) 6000 mm X (H) 1800 mm |
| 3 | Master Leaf Size | 5500 X 1800 mm & 4000 X 1800 mm |
| 4 | 1 ST Leaf Size | 5500 X 1800 mm & 4000 X 1800 mm |
| 6 | Opening Direction | Horizontal - from left to right or reverse |
| 7 | Mounting Location area | Inside area |
| 8 | Design Pattern | Standard Tubular Design Pattern |
| 9 | Outer Frame Tube Sizes | 50X50X3.2 MM THK SQ. TUBE |
| 10 | Internal Vertical Tube Sizes | 25x25x2.6mm MS SQ. TUBE |
| 11 | For Post | 50X50X3.2 MM THK SQ. TUBE |
| 12 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 13 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings |
| 14 | Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| 15 | Painting | Two Coats of Primer and Two Coats of Synthetic Enamel Paint |
| 16 | Control Panel | 2 Nos Operating Station.( Motor Panel and Security Room) |
| 17 | Operation | By Telescopic Mechanism |
| 18 | Accessories | 1. Limit Switch for Cut out when Gate is fully Closed |
| | | 2. Flashing Light |
| | | 3. Remote |
| | | 4. Hooter |
| | | 5. Photocell |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd