NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Volumnus Developers Pvt Ltd
Greenbase Industrial & Logistics Park
Hiranandani Park, Thriveni Academy, Vadakkupattu - Post,
Kanchipuram District, Chennai - 603204

Project, Location : Hiranandani, Chennai

Date : 21.1.2021
Quote NO : SQT.20.21.2957
Kind Attn : P.Murugan
Email Id : pmurugan@hrealty.com
Contact No: 9360330236

Subject : Quotation for Rolling Shutter and Fold Up Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	4000	5000	1	160,000	160,000	20,000	20,000
2	**Motorized Rolling Shutter**	4000	4000	3	140,000	420,000	20,000	60,000
3	**Motorized Rolling Shutter**	3000	2450	1	97,000	97,000	20,000	20,000
4	**Motorized Rolling Shutter**	2450	3000	6	97,000	582,000	20,000	120,000
5	**Motorized Rolling Shutter**	2400	2450	9	89,000	801,000	20,000	180,000
6	**Fold-Up Doors**	10000	10000	4	656,000	2,624,000	25,000	100,000
	Total			**24**		**4,684,000**		**500,000**
7	P&F Charges			3%		140,520		
	Total Without Taxes					4,824,520		500,000
	GST Extra @ 18%			18%		868,413.60		90,000
	Total With Taxes					**5,692,934**		**590,000**
8	Transportation Charges					Extra at atcual		
9	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection



Fold Up Door

Sr. No.	Description	Specification
1	Product	High Speed Door-Fold up type (All Imported Components)
2	Opening Direction	Vertical
3	Mounting Location	Inside of the bay, inside the building
4	Opening/Closing Speed	0.5m/Sec. -1.0m/Sec.
5	Wind Resistance	90km/h – 110 km/h
6	Curtain Material	Curtain is in PVC made by anti-tear polyester fabric
7	Curtain Weight	680 gr/sqm
8	Tensile Strength Warp/Weft (N/5Cm)	DIN 53354 - DIN EN ISO 1421/met. 1 – 2500/2500 N/50 mm
9	Stiffeners	Polycorbinate pipes
10	Tear Strength	Warp/Weft DIN 53363 – 250/250 N
11	Temperature range	-30°C +70°C
12	Flame Resistance	reaction in class 1 or 2
13	Vision Panel	One row of transparent PVC windows, in rectangular size, assures a good visibility
14	Fabric Color	Standard Blue, Grey, Red, Optional with various colors
15	Fold Up Arrangement	Segmented PVC curtain is folded up through lifting belt & tube mechanism
16	Roller Shaft	Tubular pipes with lifting belts
17	Side Guide Rails	Self supporting Galvanized steel structure
18	Bottom Profile	PVC profile
18	Side Brackets	Galvanized steel brackets with bearings
19	Hood Cover (Optional)	Galvanized steel

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd