NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

INTEGRATED CONVEYORS AND PACLINE AUTOMATION TECHNOLOGIES
Coimbatore

Date : 03.02.2022
Quote NO : **MHE_21.22.0057**
Kind Attn : Mr. Sengathir S
Email Id : sengathir@integratedconveyors.com
Contact No: 87540 16772

Project Name & Location: ITC, Coimbatore

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor** • Total Length- 18.5mtr (Fixed-6mtr, Extended-12.5mtr) • Capacity- 50kg/mtr • Belt Width - 600 mm	1	15,50,000	15,50,000	Client Scope	
	TOTAL EXCLUDING TAXES					**15,50,000**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	P&F Charges	3%				**Extra At Actual**
4	Transportation Charges					**Extra At Actual**
5	Insurance Charges					**Extra At Actual**
6	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Bags
2	Capacity	50 kg /mtr
3	Belt Width	600 mm
4	Belt Type	Smooth Top 2 Ply, PVC Coated Endless type Omron Make
5	Belt Speed	15-30 mtr/min
6	Length Of Conveyor	Fixed Length : 6000 mm Telescopic (Expanded) : 12500 mm Total Length : 18500 mm
7	Main Body Of Conveyor	MS Powder coated
8	Belt Direction	Both Forward and Reverse direction
9	Max. Working height	900 mm to 1900 mm
10	Speed adjustment	VFD (Schneider / Allen Bradley/Delta)
11	Lifting Mechanism	Hydraulic power packs
12	Gear Box	Bonfiglioli
13	Motor Make	Siemens, IE2
14	Movement	Fixed (No wheels)

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost .

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd