Purchase Order

C.P.O.: 2500043118 Date: 30.05.2022

TO, Vendor Code : 705277
NIHVA TECHNOLOGIES PVT. LTD.
SAMEER PLAZA FIRST FLOOR,
G-BLOCK,THERMAX CHOWK,
CHINCHWAD.
PUNE 411044
Phone No. :
Mobile No.:
Fax No. :
PAN : AAECN0437H
GSTIN : 27AAECN0437H1ZM

INSURANCE TO BE COVERED BY YOU.

Delivery Address/ Consignee : EP24

EMCURE PHARMACEUTICALS LTD- IV
100% EOU DIVISION,P-2,I.T.B.T.PARK,
PHASE-II MIDC,HINJAWADI,TA:MULSI,
PUNE 411057
Maharashtra
D.L.No.: DL:PD-93 PD-149 DT 04.09

Bill to : EMCURE PHARMACEUTICALS LTD- IV
100% EOU DIVISION,P-2,I.T.B.T.PARK,
PHASE-II MIDC,HINJAWADI,TA:MULSI,
PUNE 411057
28-PD/101
GSTIN : 27AAACE4574C1ZV

PAN : AAACE4574C
CIN : U24231PN1981PLC024251

Kindly confirm acceptance of this order with your shipment/deliveryschedule. The materials/services specified in this purchase order is subject to terms and conditions printed overleaf, which are in addition to instructions and specification given in this document.Please quote this purchase order number and date in all your correspondence, despatch documents and invoices.

Material Code Description	QTY Ordered	UOM	Basic Rate	CGST	SGST	TCS	Total Value/Unit	Other	Total Value
Specification No. Make	HSN/SAC Code			Currency:INR					

951021243 PIT MOUNT ELECTRO HYDRAULIC SCISSOR LIFT

PR 7200257457	**04.04.2022**	**1.000NOS**	**350,000.00**	**49,000.00**	**49,000.00**	**0.00**	**448,000.00**	**0.00**	**448,000.00**
		84282019		**14.00 %**	**14.00 %**	**0.000 %**			

TYPE:PIT MOUNTED, CAPACITY 3000 KG. PLATFORM 2600L MM x 1750W MM.
MINIMUM HEIGHT 500 MM, MAX. HEIGHT 1500MM. LIFT HEGHT 1000MM.
LATFORM TYPE:CHEQUERED. LOADING/UNLOADING SITE FROM WIDTH SIDE.
LOADING CONDITION : UNIFORMLY DISTRIBUTED LOAD REQUIRED
RALING 2 SIDE REMOVEABLE RAILING,1 SIDE OPEN.
RAILING HEIGHT 900 MM, FLAP SIZE : 1750 X 400 MM X 5THK.
FLAP OPERATION 1 SIDE HYDRAULIC FLAP. NO OF SCISSOR PAIR I,
NO OF CYLINDER I. MOTOR 5 HP, PUSH BUTTON SCHNIEDR, CABLES
POLYCAB OR EQUIVALENT MOC MS WITH GOLDEN YELLOW ENAMEL PAINT FINISH.

Delivery Schedule:	**Delivery Quantity**	**Delivery Schedule Date**
	1.000	**04.07.2022**

951021243 INSTALLATION & COMISSIONING CHARGES

PR 7200257457	**04.04.2022**	**1.000NOS**	**0.00**	**0.00**	**0.00**	**0.00**	**0.00**	**0.00**	**0.00**
		84282019		**14.00 %**	**14.00 %**	**0.000 %**			

DRAWING APPROVAL TO BE TAKEN FROM EMCURE PRIOR TO PRODUCTION.
=======
P&F CHARGES INCLUSIVE.
TRANSPORT CHARGES INCLUSIVE. - INSTALLATION, TESTING, COMISSIONING & OPERATOR TRAINING CHARGES INCLUSIVE.
--
WARRANTY ONE YEAR.

PAYMENT TERMS : 30% ADVANCE ALONG PURCHASE ORDER AGAINST PI, 50% AGAINST PERFORMA INVOICE BEFORE DISPATCH & BALANCE 20% AFTER INSTALLATION & HANDOVER.
REF. QUOTATION REFERENCE NO AS_22.23.0008 DT. 24.05.2022.

Delivery Schedule:	**Delivery Quantity**	**Delivery Schedule Date**
	1.000	**04.07.2022**

Basic Total: 350,000.00	**GrandTotal : 448,000.00 INR**

Terms & Conditions:

Purchase Order

C.P.O.: 2500043118 Date: 30.05.2022

Material Code Description	QTY Ordered	UOM	Basic Rate	CGST	SGST	TCS	Total Value/Unit	Other Total Value
Specification No. Make	HSN/SAC Code			Currency:INR				

a .Certificate of Analysis should accompany the consignment.
b. Please deliver the goods in minimum batches.

Terms of Payment:

FOR : EMCURE HINJWADI PH 2
P014 : Payment as per agreed norms
CRN NO EP24/WHD/03-22 DT 04.04.2022
MR. LAHU PATIL.
EMCURE PL IV WHD.

"The supplier is required to timely deposited the tax amount charged in the invoice to the Government and the same needs to be declared properly and timely in all the applicable GST returns (GSTR-1, GSTR-3B). In case of any failure of GST compliance, the supplier will make good the loss suffered by the recipient. We reserve the right to recover the tax credit loss along with interest and penalty or deduct the amount equivalent to the said liabilities from the outstanding payment.
Supplier shall ensure that Invoice, E-way bill and E-invoice is generated in the form and manner prescribed under GST Law."

Emcure Pharmaceuticals Ltd

Authorised Signatories