NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tirupati Sugar Ltd.
Bihar

Date : 03.09.2019
Quote NO : SQT.19.20.2008R
Kind Attn : Mr.Ankur Aggarwal
Email Id : ankur.tsl@yadu.in
Contact No: **7982184081**

Project Name & Location: Tirupati Sugar Ltd., Bihar

Subject : Revised Quotation for Motorised Single Leaf Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Single Leaf Gate	8000	2500	1	4,95,000	4,95,000	20,000	20,000
				Total		**4,95,000**		**20,000**
2	P&F Charges			3%		**14,850**		
	Total Without Taxes					**5,09,850**		**20,000**
	GST Extra @ 18%			18%		91,773		3,600
	Total With Taxes					**6,01,623**		**23,600**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications
1	**Door type**	Motorised Single Leaf Sliding Gate
2	**Clear Opening gate dimension**	(W) 8000 mm X (H) 2500 mm
3	**Opening Direction**	Horizontal - from left to right or reverse
4	**Mounting Location area**	Inside area
5	**Design Pattern**	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	72 x 72 x 3.2 mm
7	**Internal Vertical Tube Sizes**	38 x 38 x 3.2 mm
8	**Gap Between Tubes**	125 mm C/C
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Full Height Column sizes**	100 x 100 x 3.2 mm
12	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
13	**Painting**	Powder Coating
14	**Metal Rack**	Zinc plated metal rack
15	**Installation Checks**	need to be check = space requirements + substructure + Mounting access

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Swapnil Kulat on 7219207333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd