NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

A) Commercial Offer

Sr.	Material Description	Width (mm)	Height (mm)	Qty.	Unit	NIHVA Technologies			
						SQT.19-20.2082			
						Arjun Patil			
						Supply		Installation	
						Rate	Amount	Rate	Amount
1	Motorised Rolling Shutter 1. Curtain made of double skinned galvanised steel laths with PUF Insulation 2. Surface precoated in RAL 9006 3.Pressed galvalume steel hood & motor cover with two coats of Polyurethane spray paint similar to RAL 9006 over one coat of epoxy primer 4. CE Certified CRS Compact Gear P.R.C. Make Indirect Drive Operator 5. Three station push button with deadman control	2160	2400	1	No	114000.00	114000.00	20000.00	20000.00
2	MS Support Structure - MS structure made of 100x50mm ISMC with one coat of grey epoxy primer by spray	2160	2400	1	No	35000.00	35000.00	0.00	0.00
							149000.00		20000.00
P&F						3.00%	4470.00	0.00%	0.00
							153470.00		20000.00
Freight & Insurance						10.00%	15347.00	0.00%	0.00
							168817.00		20000.00
GST						18.00%	30387.06	18.00%	3600.00
							199204.06		**23600.00**
Total Value						**222804.06**			
P&F						As mentioned above			
Freight & Insurance						As mentioned above			
Delivery Schedule									
Lead period for supply						4 - 5 Weeks from date of receipt of conform purchase order			
Lead period for Installation						2-3 Days			
Warranty						12 Months from date of supply			
Payment Terms for supply						80% advance & 20 % before dispatch			
Payment Terms for installation						100 % after completion of Installation			

B) Technical Specification provided by NIHVA Technologies

Motorised Rolling Shutter

1. Curtain made of double skinned galvanised steel laths with PUF Insulation
2. Surface precoated in RAL 9006
3.Pressed galvanised steel hood & motor cover with two coats of Polyurethane spray paint
4. Compact Gear Jielong Make Indirect Drive Operator
5. Three station push button with deadman control
6. GI Slat : 19 mm Thick
7. Profile : Curved Type Profile with heavy duty Shaft
8. Guide : 2.5 mm Thick MS Guide
9. Hood Cover & Motor Cover : 0.9 mm Thick GI material

MS Support Structure
MS structure made of 100x50mm ISMC with one coat of grey epoxy primer by spray

C) **General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.
2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: **Please find below List which are in Client Scope**

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) **Terms & Conditions**

Price : Ex Works Pune
Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd