NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

L&T Constructions
Hyderabad

Date : 08.03.2021
Quote NO : SQT.20.21.3079
Kind Attn : Mr. Ramprakash
Email Id : Meetram@Intecc.com
Contact No: 99404 87276

Project, Location : Airport Village Project Hyderabad

Subject : Quotation for Vertical Stacking Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option I	Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Vertical Stacking Door**	6000	2400	5	6,965,575	34,827,875	250,000	1,250,000
2	**Vertical Stacking Door**	6000	4000	5	10,448,363	52,241,815	375,000	1,875,000
	Total			**10**		**87,069,690**		**3,125,000**
3	P&F Charges			3%		2,612,091		
	Total Without Taxes					89,681,781		3,125,000
	GST Extra @ 18%			18%		16,142,720.53		562,500
	Total With Taxes					**105,824,501**		**3,687,500**
4	Transportation Charges					Inclusive		
5	Unloading Charges @ Site					In Client Scope		

Note : Including Glazing - Polycarbonate

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Vertical Stacking Door

Sr. No	Description	Specifications
1	**APPLICATION**	EXTERNAL
2	**CLEAR OPENING HEIGHT**	4000 mm / 2400 mm
3	**CLEAR OPENING WIDTH**	6000 mm
4	**HEADROOM**	570 mm / 470 mm
5	**SIDE ROOM - MOTOR SIDE**	320 mm
6	**SIDEROOM - NON MOTOR SIDE**	90 mm
7	**FRAME MATERIAL**	GALVANISED STEEL
8	**CURTAIN MATERIAL**	FULLY GLAZED
9	**VISION PANEL**	DOUBLE GLAZED, 17mm POLYCARBONATE
10	**BOTTOM OF VISION**	FULLY GLAZED
11	**TOP OF VISION**	FULLY GLAZED
12	**MOTORISATION**	IP54 RATED 3 PHASE MOTOR DRIVE & ELECTROMAGETIC BRAKE
13	**MOTOR POSITION**	RIGHT HAND
14	**CONTROL PANEL**	RIGHT HAND
15	**POWER SUPPLY**	3 PHASE, 400V + NEUTRAL + EARTH 16 Amp
16	**ACTIVATION INSIDE**	PUSH BUTTON

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 Months from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd