NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mahansaria Tyres Pvt. Ltd
612, 6th Floor, Maker Chamber IV
Nariman Point, Mumbai 400 021

Date : 19.11.2020
Quote NO : SQT.20-21.2830
Kind Attn : Manjunath Patil
Email Id : manjunath.patil@ascensotyres.com
Contact No: 8007775228

Subject : Quotation for Sliding Gate & Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	AUTOMATIC SINGLE LEAF SLIDING GATE - with 2 mm thickness sheet single side	7120	1800	1	426,000	426,000	20,000	20,000
2	AUTOMATIC SINGLE LEAF SLIDING GATE	7120	1800	1	384,000	384,000	20,000	20,000
4	AUTOMATIC Bi- Parting BOOM BARRIER	4000		2	110,000	220,000	15,000	30,000
5	AUTOMATIC Bi-Parting BOOM BARRIER	5000		4	110,000	440,000	15,000	60,000
			Total Value			**1,470,000**		**130,000**
6			**P&F Charges**	3%		44,100		
			Total Without Taxes			**1,514,100**		**130,000**
			GST Extra @ 18%	18%		272,538		23,400
			Total With Taxes			**1,786,638**		**153,400**
7			Transportation Charges			**Extra at actual**		
8			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Sr. No	Description	Specifications
1	Door type	Motorised Sliding Gate
2	Clear Opening gate dimension	1) (W) 7120 mm X (H) 1800 mm - With Sheet one side 2) (W) 7120 mm X (H) 1800 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	72 x 72 x 3.2mm MS SQ. TUBE
7	Internal Vertical Tube Sizes	30 x 30 x 3.20mm MS SQ. TUBE
8	For Post	72 x 72 x 3.2mm MS SQ. TUBE
9	GI Sheet	2 mm thickness - Single side
10	Gap Between Tubes	125mm
11	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
13	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
15	Motor	100% Imported from Europe
16	Safety	Photocell, Flashing Light

Boom Barrier





Sr. No.	Description	Specifications
1	Size	4/5 Mtr
2	Make	Nice/BFT
3	Opening time	Opening Time- 4S
4	Motor Power Supply	24V
5	Type of limit Switch	Electronic
6	Safety	Photocell sensor
7	Operated	Push Button Pedant

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	
8	Lifting Equipements	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd