Sales Quotation

Quotation No - SQT/19-20/1716 **Date :18.06.2019**

Ordnance Factory Board ,
High Explosive factory,
Near Holkar Bridge, Khadki, Pune

Kind Attn: Mr. R. N. Gaikwad.
Email: suhasgurav.ofd@ofd.gov.in
Contact No: 2025322231

Project Name And Location : Khadki, Pune.

Subject : Quotation for Conveyor System.

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Telescopic Conveyor** **(Supply + Installation)**				
1	Conveyor Type : Telescopic Capacity : 60 kg / metre Total Length : 9000 mm Collapsed length :5000 Height : 900 mm Safety Sensor at front with LED Light Operational Flashing lamp Speed : 2mtr / min Include Following - • Mechanical Structure • Machining Components • Mechanical Bought out (Taper Roller Bearing, Ball Bearings , Sprockets , Guide Roller , Couplings , Rubber rollers , Chain , Sprocket , Caster wheel , hydraullic cylinder & power pack) • Electrical Bought out (Drive Motor (3 hp) , Drive Motor(2 hp) ,Relay Contacter , VFD Drive , Control Panel , Sensors , Limit switch , Flashing lamp , LED Lights , Syren)	1	No	2,565,500	2,565,500
				Total	2,565,500

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
B	**Roller Conveyor** **(Supply + Installation)**				
1	Conveyor Type : Roller Conveyor Capacity : 60 kg / metre Total Length : 5500 mm Height : 900 mm Speed : 1 mtr / min Include Following - • Mechanical Structure • Machining Components • Mechanical Bought out (Drive Roller (MS Galvanised) , Pop Conveyor belt , Pneumatic Cylinder, Drive Chain, Caster Wheel) • Electrical Bought out (Drive motor (2 hp) , Drive Motor (0.75hp) , VFD Drive , Control Panel , Sensors , Limit switch , Reed Switch ,Solenoid valve)	1	No	1,786,800	1,786,800
				Total	1,786,800
C	**Roller Conveyor** **(Supply + Installation)**				
1	Conveyor Type :Roller Conveyor Capacity : 60 kg / metre Total Length : 9500 mm Height : 900 mm Speed : 1 mtr / min Include Following - • Mechanical Structure • Machining Components • Mechanical Bought out (Drive Roller (MS Galvanised) , Pop Conveyor belt , Pneumatic Cylinder , Drive Chain , Caster Wheel) • Electrical Bought out (Drive motor (2 hp), Drive Motor (0.75hp) , Control Panel , Sensors , Reed Switch ,Solenoid valve)	1	No	1,582,700	1,582,700
				Total	1,582,700
D	**Gravity Roller Conveyor** **(Supply + Installation)**				
1	Gravity Roller Conveyor Capacity : 60 kg / metre Total Length :6500 mm Height : 900 mm to 400 mm Include Following - • Mechanical Structure • Machining Components • Mechanical Bought out (idle Roller (MS Galvanised) , Caster Whee)	1	No	913,300	913,300
				Total	913,300

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**6,848,300**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Swapnil Kulat - 7219207333** For any further Clarification /Information in this concern.

With Best Regards

Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd