NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Denasa Buildcon
C-3, Sant Tukaram Vyapar Sankul, First Floor
Sector 24, Pradhikaran, Nigdi, Above Hotel Savali,
Pune - 411044.

Date : 6.10.2020
Quote NO : SQT.20.21.2738
Kind Attn : Mahesh Pawar
Email Id : mahesh.p@denasaindia.com
Contact No: 8308810541

Project Name & Location: Tamilnadu

Subject : Quotation for Motorised Rolling Shutter, Dock Leveler, Dock Shelter and Sliding Glass Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	5000	6000	2	203,000	406,000	20,000	40,000
2	Motorized Rolling Shutter	3000	4000	4	113,000	452,000	20,000	80,000
3	Automatic Sectional Door Vertical Lift	3000	4000	19	360,000	6,840,000	20,000	380,000
4	Dock Leveller 9 Ton	2200	3000	21	250,000	5,250,000	20,000	420,000
5	Retractable Dock Shelter	3000	4000	21	140,000	2,940,000	20,000	420,000
6	Sliding Glass Door	2000	2400	3	310,000	930,000	20,000	60,000
7	High Speed Door RR300 Plus Alu	4200	3500	1	714,000	714,000	20,000	20,000
8	High Speed Door RR300 Plus Alu	3500	4200	1	715,000	715,000	20,000	20,000
9	High Speed Door RR300 Plus Alu	3000	3000	1	659,000	659,000	20,000	20,000
				Total		**18,906,000**		**1,460,000**
10	P&F Charges			3%		**567,180**		
	Total Without Taxes					**19,473,180**		**1,460,000**
	GST Extra @ 18%			18%		3,505,172		262,800
	Total With Taxes					**22,978,352**		**1,722,800**
11	Transportation Charges					**Extra at Actual**		
12	Unloading Charges @ Site					**Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Honeycomb Grill**	600mm grill at 3000mm height from Bottom.
14	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Dock Leveler

Sr. No.	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	0.1
11	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L)3050 mm x (D)485 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

NIHVA ASSA ABLOY Sectional Door

Sr. No	Description	Specifications
1	**Model No**	OH1042P
2	**Opening Direction & Mounting**	Vertical
3	**Door produced Based on which certific**	Doors produced according to ISO 9000 or ISO 14000 certified.
4	**Opening/Closing Speed**	0,28 m/s
5	**Door Material**	GI Steel
6	**Panel Thickness**	44 mm
7	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	**Water Penetration**	EN 12425 class 3
9	**Air Permealibity**	EN12426 class 3
10	**Wind Load**	EN21424 class 3
11	**Thermal Transittance**	6 W/m2K
12	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	**Emergency Operation**	Single phase 230V direct drive on shaft
14	**Operating Switch**	by Disengagement rope manual
15	**Environmental Green Product Declarat**	Up/Down Keypad + stopbutton
16	**Drive Unit & Mounting Type**	as per ISO 14025 and EN 15804

Retractable Dock Shelter

Sr. No	Description	Specifications
1	**Size**	(W) 3600 mm x (H) 4500 mm
2	**Top Curtain**	1000 mm
3	**Side Curtain**	600 mm
4	**Curtain colour**	Black
5	**Parking Guides**	White, Yellow
6	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
7	**Top & Side Curtaiins**	Double Layer High Quality Polyester
8	**Thickness**	3.0 mm
9	**Weight**	Approx 3400 g/m2

ASSA ABLOY-BESAM-Automatic Sliding Door SL 500

	100% imported from Sweden
Sr. No	**Specifications :**
1	**Main power supply**
2	**Operator type- Bi part operator.**
3	**User interface- Auto Partial/Auto/one way/closed including LED status**
4	**Battery- Battery 12 V power fail open**
5	**open Operator lock- Electric lock (fail safe)**
6	**Glass : 10mm thick toughened glass**
7	**Wide acid / dip acid printing of your Logo.**

High Speed Door

Sr. No	Description	Albany Make Rapid Roll Up Door RR300 Plus Aluminium
1	Construction:	Transparent PVC with blue (RAL 5002) or red (RAL 3002) reinforcement stripes.
2	Side Frames :	Aluminium profiles, anodised
3	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
4	Self Opening :	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
5	Control system:	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down
6	Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.
7	Safety features:	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7588220333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd