NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

John Deere India Pvt Ltd
Sanasawadi
Pune - 412208

Date : 17.06.2020
Quote NO : SQT/19-20/2498R5
Kind Attn : Mr. Vinayak Kulkarni
Email Id : KulkarniVinayak@johndeere.com
Contact No: 9284773895

Subject : Quotation for NIHVA make High Speed Door for External Applications

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Roll Up Fast Aluminum Door**	3000	4000	1	3,75,000	3,75,000	15,000	15,000
2	**Radar Sensor**			2	15,000	30,000		-
3	**AMC Charges for a period of one year (4 Visits)**			1	35,000	35,000		-
				Total		**4,40,000**		**15,000**
4				P&F Charges	NIL			
				Total Without Taxes		4,40,000		15,000
				GST Extra @ 18%	18%	79,200		2,700
				Total With Taxes		**5,19,200**		**17,700**
5				Transportation Charges		Included in above Prices		
6				Unloading Charges @ Site		NIHVA Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Aluminum Insulated Metal Door		
Sr. No	**Description**	**Details**
		High Speed Door_External Door
1	Door construction:	Polyurethane filled RAL 9006 aluminium lamella
2	Side Frames	Aluminum anodised
3	Door Curtain	Aluminum 19 mm thick panel
4	Wind resistance:	EN12424 - Class 3
5	Protection	Operator - IP54 and Ccotrol Panel - IP65
6	Control system:	Open - stop - close button and emergency stop switch
7	Speed:	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking Opening Speed - 1 m/s Closing Speed - 0.7 m/s
8	Safety device:	Photocell, safety edge
9	Manual activation :	Crank Handle
10	Motor and Hood Cover	GI 0.8mm thick

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd