**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Amber Enterprises India Ltd.**
MIDC Rajangaon

**Date : 24.08.2019**
Quote NO : SQT.19.20.1971
**Kind Attn :** Mr. Rahul Borhade
Email Id : rahulborhade@ambergroupindia.com
Contact No: 9764867750

**Project Name & Location: Amber Enterprises India Ltd. And Rajangaon**

**Subject : Quotation for Scissor Lift**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **NIHVA Scissor Lift<br>Floor Mounted Scissor Lift<br>Capacity 2 Ton** | 2500 | 2700 | 1 | 445,600 | 445,600 | NA | NA |
| | | | | **Total** | | **445,600** | | |
| 2 | P&F Charges | | | 3% | | **13,368** | | |
| | **Total Without Taxes** | | | | | **458,968** | | |
| | GST Extra @ 18% | | | 18% | | 82,614 | | - |
| | **Total With Taxes** | | | | | **541,582** | | **-** |
| 4 | Transportation Charges | | | | | **In Client Scope** | | |
| 5 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| NIHVA make – FLOOR MOUNTED SCISSOR LIFT | |
|---|---|
| Capacity | **2 TON** |
| Platform Size | 2700L x 2500W |
| Shut ht | **350 mm** |
| Max ht | 2200 mm |
| Lift ht | 1850 mm |
| Power pack | 3 HP, 3 PH |
| Safety railing | both length side only |
| Safety parameters | 1. Pilot operated check valve.<br>2. Buzzer while operation UP & DOWN.<br>3. Max ht limit switch.<br>4. Over load relay for control panel. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | NIHVA Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.swapnil kulat on 7219207333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd