**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Amalgam Design Lab Pvt Ltd**
Navi Mumbai

**Date :** 29.01.2025
**Quote NO :** RR_24.25.0168
**Kind Attn :** Ms. Riya
**Email Id :**
**Contact No:** 877098 9846

**Project Name & Location:** Navi Mumbai

**Subject : Commercial Offer for Automatic Retractable Roof.**

**Dear Sir,**
**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 1 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |

**A) Commercial Offer**

| Sr No | Description | Size (mtr) | Qty | Supply & Installation Charges in INR | |
|---|---|---|---|---|---|
| | | | (Nos) | Unit Rate | Total |
| 1 | **Automatic Retractable Roof (With Polycarbonate sheet)** | • W 2306 mm X L 9938 mm<br>• 4 Panel, one side opening<br>• 3mm Polycarbonate<br>• Installation Inclusive | 1 | ₹ 9,50,000 | **₹ 9,50,000** |
| 2 | | **Total without Taxes** | | **₹** | **9,50,000** |
| 3 | | GST Extra @ 18% | 18% | | **Extra At Actual** |
| 4 | | P&F Charges @ 3% | 3% | | **Extra At Actual** |
| 5 | | Transportation Charges | | | **In Client Scope** |
| 6 | | Unloading Charges @ Site | | | **In Client Scope** |

**B) Technical Specification**

| |
|---|
| **1. Polycarbonate Compact Clear/Embossed 3.0 mm Thick** |
| **2. Profile : Powder Coated Ms+AL Frame** |
| **3. Guide : Powder coated MS Guide** |
| **4. Interlocking** |
| **5. Motor Mechanism with control panel**<br>**a) Push - button Controlled**<br>**b) Single Phase Bi-directional Motor**<br>**c) Speed- 09-12m/min**<br>**d) Power- As per Roof Dimension**<br>**e) Mechanical Limit Switch**<br>**f) Rack and Pinion Arrangement** |
| **6. EPDM Gaskets and sealants** |
| **7. SS Fastners** |



**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

| | |
|---|---|
| 1 | Continuous uninterrupted access to installation section or as agreed seperately. |
| 2 | Provision of 230 V power supply for hand tools. |
| 3 | A dry and secure area, not in direct sunlight is to be provided for storage of product component |
| 4 | Access to site between 7 am to 8 pm should be provided. |
| 5 | Any storage costs for material due to delay outside of NIHVA, will be in client scope. |
| 6 | The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly. |
| 7 | Installation will start after receiving of Site Readiness Photographs or written Email communication. |
| 8 | We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation. |
| 9 | For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team. |
| 10 | If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope. |
| 11 | After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost. |

**Note:** **Please find below List which are in Client Scope**

| Sr. No | | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material. | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site. | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required. | In Client Scope |
| 5 | All structure support required. | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

| | |
|---|---|
| **Price :** | Ex Works Pune. |
| **Delivery :** | 6-8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval. |
| **Payment :** | 70% Advance along with Confirmed Purchase Order.<br>20% After material Delivery at site.<br>10% After Installation. |
| **Validity :** | Validity of offer is 15 days from the date of quotation. |
| **Warranty :** | 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity. |

**With Best Regards**
Priyanka Pachange
7410169333
NIHVA Technologies Pvt Ltd