NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Raj Group
Gujrat

Date : 08.05.2021
Quote NO : **MHE_21.22.0008**
Kind Attn : Mr. Vishal Gurav
Email Id : vishal.gurav@rajgrp.com.
Contact No: 9328540013

Project Name & Location: ELECTRO HYDRAULIC GOODS LIFT, Gujrat

Subject : Quotation for ELECTRO HYDRAULIC GOODS LIFT

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specifications	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ELECTRO HYDRAULIC GOODS LIFT** Platform size-1300 mm (L) x 1000 mm (W) Max.Lifting height- 11200 mm Capacity- 1000 kg.	1	5,52,000	5,52,000	35,000	35,000
	Total			5,52,000		35,000
	P&F Charges	3%		16,560		
	Total Amount Without Tax			5,68,560		35,000
	GST Extra @ 18%	18%		1,02,341		6,300
	Total Amount Inlcuding Tax			6,70,901		41,300
2	**Transportation Charges**					**Extra At Actual**
3	**Unloading Charges @ Site**					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specifications

ELECTRO HYDRAULIC GOODS LIFT

Sr.No.	Parameters	Specifications
1	Platform Size	1300 mm (L) x 1000 mm (W)
2	Capacity	1000 Kgs
3	Lowered Height	200 mm
4	Max. Lift Height	11200 mm
5	No's of Mast	Single Mast
6	No's of Cylinder	1
7	Electric Motor	3 HP
8	Power Supply	3 ph , 415V AC
9	Lifting Speed	3 m per min
10	Operating Pendant 2 nos (G+1) (Ground + First Floor)	UP / Down
11	Operation	Auto + Inching Mode Lift Operation
12	Safety Railing & Hinged Door - Ht 900 mm	3 Side Safety Railing and 1 Side Openable Door

C) General Conditions:

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 6-8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd