NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Krisam Automation Pvt Ltd
SPL 4, Main Road 3, KSSIDC Industrial Estate
II nd Phase, Jigni, Bangalore - 560105, India

Date : 22.07.2020
Quote NO : SQT/19-20/0025
Kind Attn : Mr. Akash Kumar Gupta
Email Id : akash@krisamautomation.com
Contact No: 9628433165

Subject : Quotation for Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ELECTRO HYDRAULIC SCISSOR LIFT (PIT MOUNTED) Capacity - 3 Ton**	1500	1500	1	5,45,000	5,45,000	25,000	25,000
2	**ELECTRO HYDRAULIC SCISSOR LIFT (PIT MOUNTED) Capacity - 4 Ton**	1500	1500	1	5,75,000	5,75,000	25,000	25,000
				Total		**11,20,000**		**50,000**
3	P&F Charges			3%		33,600		
	Total Without Taxes					11,53,600		50,000
	GST Extra @ 18%			18%		2,07,648.00		9,000
	Total With Taxes					**13,61,248**		**59,000**
4	Transportation Charges					Extra at Actaul		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification : Pit Mounted Scissor Lift

Sr. No	Description	Details	Details
1	Capacity	3 Ton	4 Ton
2	Platform	1500 (L) x 1500 (W) mm	1500 (L) x 1500 (W) mm
3	Shut Height	700 mm	800 mm
4	Lift Height	2500 mm	2500 mm
5	Max Height	3200 mm	3300 mm
6	POWER PACK	5 HP , 3 PH	5 HP , 3 PH
7	Oil Tank	65 Ltr	65 Ltr
8	RAILING ON BOTH LENGTH SIDE 900 MM HT.	SS304	SS304
9	TOP CHEQ.SHEET	SS304	SS304
10	PAINT (RAL 1004)	GOLDEN YELLOW	GOLDEN YELLOW
11	SAFETY BELLOW	ALL SIDE	ALL SIDE

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7- 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd