NIHVA
NIHVA Technologies Pvt. Ltd.

BILL OF MATERIAL

Format No.: NIHVA-DEG-F-06	
Revision No.:00	
Revision Date :	
Date of Origin :01-01-2017	
Project Number:	
Customer :Rewards Construction	
Width (mm)	**9000**
Height (mm)	**1800**
Quantity	**1**

PRODUCT - MOTORISED SINGLE LEAF SLIDING GATE

SR NO	PART NAME	SEGMENT	MATERIAL	LENGTH (M)	QUANTITY FOR 1	UNIT	REMARK
1	Outer frame tube (100x50x2.5)	Mechanical	M.S	10	3	nos	
2	Outer frame tube (100x50x2.5)	Mechanical	M.S	1.8	2	nos	
3	Inner tube (25x25x2.0mm)	Mechanical	M.S	1	98	nos	
4	Inner tube (100x50x2.5)	Mechanical	M.S	0.5	4	nos	
5	Perforated sheet (560x1950x2.0mm)	Mechanical	M.S		5	nos	as per drawing
6	Guide post (70x70x3.0mm)	Mechanical	M.S	1.9	4	nos	as per drawing
7	Guide post plate With laser cut (70x272x5.0mm)	Mechanical	M.S		4	nos	as per drawing
8	Guide post plate (70x200x5.0mm)	Mechanical	M.S		4	nos	
9	Guide post Bottom plate (1120x170x10.0mm)	Mechanical	M.S		4	nos	as per drawing
10	En8 Bar	STD	En8	19	1	nos	
11	ISMB (100x50)	STD	M.S	19	1	nos	
12	Rack & Pinion	STD		10	1	nos	
13	Nice Motor	STD			1	nos	1000kg
14	Upper guide roller With berring	STD	Nylon		8	nos	
15	Bottom Sliding wheel (Ø100)	STD			4	nos	
16	Paint	STD				Liter	
17	Thinner	STD				Liter	
18	Anchor fastener (m12x100)	STD			8	nos	
19	Anchor fastener (m12x200)	STD			16	nos	

NIHVA
NIHVA Technologies Pvt. Ltd.

BILL OF MATERIAL

Format No.: NIHVA-DEG-F-06	
Revision No.:00	
Revision Date :	
Date of Origin :01-01-2017	
Project Number:	
Customer :Rewards Construction	
Width (mm)	**9000**
Height (mm)	**1800**
Quantity	**1**

PRODUCT - MANUAL DOUBLE LEAF SWING GATE

SR NO	PART NAME	SEGMENT	MATERIAL	LENGTH (M)	QUANTITY FOR 1	UNIT	REMARK
1	Outer frame tube (100x50x2.5)	Mechanical	M.S	4.5	4	nos	
2	Outer frame tube (100x50x2.5)	Mechanical	M.S	1.8	4	nos	
3	Inner tube (25x25x2.0mm)	Mechanical	M.S	1	86	nos	
4	Inner tube (100x50x2.5)	Mechanical	M.S	0.5	4	nos	
5	Perforated sheet (560x1480x2.0mm)	Mechanical	M.S		6	nos	
6	Guide post (250x250x6.3mm)	Mechanical	M.S	2.6	2	nos	as per drawing
7	Guide post Bottom plate (500x500x16mm)	Mechanical	M.S		2	nos	as per drawing
8	Hinges With ballbearings	STD			6	nos	
9	Bottom Sliding wheel (Ø100)	STD			2	nos	
10	Manual Lock	STD			1	nos	
11	Tower Bolt	STD			2	nos	
12	Paint	STD				Liter	
13	Thinner	STD				Liter	
14	Anchor fastener (m12x100)	STD			16	nos	
15	Anchor fastener (m16x250)	STD			8	nos	

NIHVA
NIHVA Technologies Pvt. Ltd.

BILL OF MATERIAL

Format No.: NIHVA-DEG-F-06	
Revision No.:00	
Revision Date :	
Date of Origin :01-01-2017	
Project Number:	
Customer :Rewards Construction	

PRODUCT - MANUAL WICKET GATE

Width (mm)	**1500**
Height (mm)	**1500**
Quantity	**1**

SR NO	PART NAME	SEGMENT	MATERIAL	LENGTH (M)	QUANTITY FOR 1	UNIT	REMARK
1	Outer frame tube (100x50x2.5)	Mechanical	M.S	4.5	4	nos	
2	Outer frame tube (100x50x2.5)	Mechanical	M.S	1.8	4	nos	
3	Inner tube (25x25x2.0mm)	Mechanical	M.S	0.8	13	nos	
4	Perforated sheet (560x1300x2.0mm)	Mechanical	M.S		1	nos	
5	Hinges With BKT.	STD			2	nos	
6	Manual Lock	STD			1	nos	
7	Tower Bolt	STD			1	nos	
8	Paint	STD				Liter	
9	Thinner	STD				Liter	
10	Anchor fastener (m12x100)	STD			8	nos	