NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Indospace Industrial Park Pune Pvt. Ltd.
Chakan III

Date : 29.09.2020
Quote NO : SQT/20-21/2726R
Kind Attn : Tushar Dhande
Email Id : tushar.dhande@indospace.in
Contact No: 8879311890

Subject : Quotation for Manual Swing Gate and Wicket Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MANUAL BIPARTING SWING GATE**	6000	1800	**3**	190,000	570,000	20,000	60,000
2	**MANUAL WICKET GATE**	1200	1800	**3**	45,000	135,000	6,500	19,500
				Total		**705,000**		**79,500**
3	P&F Charges			3%		21,150		
	Total Without Taxes					726,150		79,500
	GST Extra @ 18%			18%		130,707.00		14,310
	Total With Taxes					**856,857**		**93,810**
4	Transportation Charges					Extra at Actual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Manual Swing Gate

Sr. No	Specification	Motoriszed Bi-Parting Swing Gate & Wicket Gate
1	**Wicket Gate Leaf Size**	1200 x 1800 mm
2	**Clear Opening gate dimension**	6000 X 1800 mm
3	**Opening Direction**	left to right or reverse
4	**Outer Tube**	80 x 40 x 3.2 mm THK SQ. TUBE
5	**Inner Tube**	40 x 40 x 2.6 mm THK SQ. TUBE
6	**Horizontal Tube**	80 x 40 x 3.2 mm THK SQ. TUBE
7	**Design Pattern**	Standard Tubular Design Pattern
8	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
9	**Civil work**	Client scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd