NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Cybernetic Technology Pvt Ltd
Pune

Date : 05.04.2022
Quote NO : **AS_22.23.0001**
Kind Attn : Mrs. Shraddha Kulkarni
Email Id : shraddha.kulkarni@cybernetik.com
Contact No: 9923659703

Project Name & Location: Cybernetic Technology Pvt Ltd, Pune

Subject : Quotation for Automatic Case Erector

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Note	2
E.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges @ Pune Location Only in INR	
		(Nos)	Unit Price	Total Amount	Total Amount	
1	**Automatic Case Erector** Length: 200mm-600mm Width: 120mm-400mm Height: 120mm-350mm • Output Speed 15-17 carton/min • Moisture > 4-5%	1	10,75,000	10,75,000	25,000	25,000
	Total without Tax			**10,75,000**		**25,000**
2	GST Extra @ 18%	18%				**Extra at Actual**
3	P&F Charges @ 3%	3%				**Extra at Actual**
4	Transportation Charges					**Extra at Actual**
5	Insurance Charges					**Extra at Actual**
6	Unloading Charges @ Site					**In Client Scope**

B) Technical Specifications

Parameters	Specification
Std. Box Dimensions Range (L x W x H)	Length: 200mm-600mm Width: 120mm-400mm Height: 120mm-350mm
Height of table	Min.-550mm Max.-700mm
Power	220V/ 50/60HZ , 300W
Air Source	>500L/min, 0.4~0.8 Mpa Opp
Moisture	> 4-5%
Touch screen/HMI	Simens/German
PLC	Simens/German
Cylinder	Airtac/Taiwan
Mid-relay	OMRON/Japan
Switch	Schneider/German
Box Specification	3ply

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 4- 5 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. Installation will start after receiving of Site Readiness Photographs or written Email communication.
5. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
6. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All Bracket support/ Structural / Civil changes	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Notes

1. If minral water box are the end product , then the cartoons are much weaker in that case our case erector will not work.
2. Creases should not get on boxes hence carton boxes should be made on high quality level - min 3 ply and should use golden paper.
3. Mositure content should not increase by 4 to 5 %
4. Square boxes are not recommended.
5. Height of the carton should not be more than length & width.
6. Length of carton should be greater than width.

E) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment :	70% Advance along with Confirmed Purchase Order. 25% Along with Approval of Drawing and before start a Production. 5% Against completion of Installation, Testing and Commissioning.
Validity :	Validity of Offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact Mr. Vijay Tarak - 855 109 3333

With Best Regards,
Pratibha Mete
85308 72333
For NIHVA Technologies Pvt Ltd