WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
FARMSON PHARMACEUTICAL GUJARAT PRIVATE LIMITED	
Address:	
UNIT-I, PLOT NO. 28-35, 40/1&2,,GIDC INDUSTRIAL ESTATE NANDESARI-391340	

PO Number:	FP1/PO/ENG2223/02624	**W. O. No-**	SO/22-23/074
PO Dated :	25-02-2023	**W. O. Date**	25-02-2023
PO Received Date:	25-02-2023	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.22.23.0379R2	**Front Sales Person**	

Dispatch Address:

FARMSON PHARMACEUTICAL GUJARAT PRIVATE LIMITED
UNIT-I, PLOT NO. 28-35, 40/1&2,,GIDC INDUSTRIAL ESTATE
NANDESARI-391340

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Motorized Single Leaf Sliding Gate W 9000 mm X H 2100 mm	Sheet 2	No	1			0	Pending
						Total	0	

Non standard items/extra requirement, if any:

B Commerical Terms:

1	**Payment Terms:**	70 % Against Proforma Invoice against readiness for Dispatch; 30% After successful commissioning		
2A	**Delivery Date as per PO:**	WITHIN 3 WEEKS OR EARLIER.	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade		Mr. Shailesh		Mr. Kiran M	Mr. Sandip	Ms. Sujata Biradar	28-02-2023

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	As per images shared.
5	**Outer Tube**	80 X 80 X 3.2mm MS SQ. TUBE
6	**For Post**	80 X 80 X 3.2mm MS SQ. TUBE
7	**Innear Tube**	80 X 40 X 2.6mm MS SQ. TUBE
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	QD Paint & QD Primer
13	**El motor make**	(100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light
17	**Civil work**	Client scope – client need to grout the I beam in concrete to create track for sliding gate