NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SUROJ BUILDCON PVT. LTD.
Bungalow No. 3, Liberty Society Phase-I,
North Main Road,
Koregaon Park, Pune 411 001,
Maharashtra, India.

Date : 05.12.2019
Quote NO : SQT/19-20/2281
Kind Attn : Shreyash Karvekar
Email Id : skarvekar@suroj.in
Contact No: 8888809639

Subject : Quotation for Rolling Shutter,Motorized Sliding Gate , High Speed Door , Turnstile and Boom Barrier.
(Project - HELICOPTER ENGINES MRO PVT LTD)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option - 1								
A	**GI Motorized Rolling Shutter**	2500	3000	8	68,000	544,000	20,000	160,000
B	**GI Motorized Rolling Shutter**	3000	3000	5	86,000	430,000	20,000	100,000
C	**GI Motorized Rolling Shutter**	4000	4000	2	132,000	264,000	20,000	40,000
Option - 2								
A	**Gear Operated Rolling Shutter**	2500	3000	8	51,000	408,000	20,000	160,000
B	**Gear Operated Rolling Shutter**	3000	3000	5	67,000	335,000	20,000	100,000
C	**Gear Operated Rolling Shutter**	4000	4000	2	102,000	204,000	20,000	40,000
3	**High Speed Door HS9020G**	2400	3000	4	486,000	1,944,000	20,000	80,000
4	**High Speed Door HS9020G**	3000	3000	3	529,000	1,587,000	20,000	60,000
5	**Single Leaf Sliding Gate**	7000	1800	1	440,000	440,000	20,000	20,000
6	**Wicket Gate**	1500	1800	1	36,000	36,000	20,000	20,000
7	**Single Sided Full Height Turnstile Gate**			1	365,000	365,000	20,000	20,000
8	**Boom Barrier 8 mtr**			1	180,000	180,000	20,000	20,000
				Total				**820,000**
9	P&F Charges			3%		-		
Total Without Taxes						-		820,000
GST Extra @ 18%				18%		-		147,600
Total With Taxes						**-**		**967,600**
10	Transportation Charges					In Client Scope		
11	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75 mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Hand Crank

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	Description:	Gear Operated Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	Operation	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	Boom Barrier
1	MICHELANGELO BT A Barrier-1No.	(Opening Time- 8S)
2	Round Boom First part	1 No.
3	Round Boom Second part	1 No.
4	Anchor Base	1 No.
5	MOB. Boom Rest	1 No.
6	Rubber Safety Profile	1 No.
7	OMEGA AT Acce	1 No.
8	Transmitter with Channels	1 No.
9	Push Button	1 No.
10	Frequency of use	Continuous
11	Motor Power Supply	24V

Single Sided Full Height Turnstile Gate:

- It has zero position of self -checking, easy for users to maintain and use.
- There is alarm notice funtion when illegal access.
- Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically.
- IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatic ally in certain time, and the potency is small, will make an alarm sound at the same time.
- Resengautomatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time.
- Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer.
- The whole system works steadily, and the noise is very low.

lock time: 0.2s; Pass rate: 35 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w; Weight:220kgMake



NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Sr. No	Description	Details
		High Speed Door **ASSAABLOY (Albany) HS9020G** **(100% Imported products from Europe)**
1	Operating speed:	Opening: up to 2 m/s , closing: 0,5 m/s .The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.
2	Wind load resistance	Class 1 (300 N/m2), maximum wind load while closing 50 N/m2.
3	Techncial details :	a. The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage.
		b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself.
		c. Vision Window - One row of 400 mm height.

NIHVA make – Motorized Sliding Gate	
Door type	**Motorized Sliding Gate**
Clear Opening gate dimension	(W) 7000 x (H) 1800…in mm
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	100 x 50 x 3.6 mm MS RECT. TUBE
Internal Vertical Tube Sizes	25 X 25 X 2.5 THK MS SQ. TUBE
Gap Between Tubes	125 mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

s

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd