NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Klassic Wheels
Ahmednagar

Date : 16.12.2022
Quote NO : **MHE_22.23.0033**
Kind Attn : Mr. Nityanand Naik
Email Id : nityanand.naik@klassicwheels.com
Contact No: 9422991704

Project Name & Location: Klassic Wheels, Ahmednagar

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor** • Total Length- 10mtr (Fixed-4mtr, Extended-6mtr) • Capacity- 35 bags per hour • Belt Width - 650 mm	1	17,00,000	17,00,000	75,000	75,000
	TOTAL EXCLUDING TAXES			17,00,000		75,000
2	GST Extra @ 18%	18%				Extra At Actual
3	P&F Charges	3%				Extra At Actual
4	Transportation Charges					In Client Scope
5	Insurance Charges					Extra At Actual
6	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loading/Unloading Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Boxes / HDPE bags/Paper bags/ Generic bags
2	Weight of box	50 Kg.
3	Capacity	35 Boxes per hour
4	Belt Width	650 mm
5	Belt Type	Smooth Top 2 Ply, PVC Coated Endless type, (Imported)
6	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
7	Length Of Conveyor	Fixed length(A) : approx . 4000mm Telescopic (expanded) : 6000 mm Total (B) : 10000 mm
8	Direction	Both Forward and Reverse direction
9	Inclination Height	Max. 1200 mm
10	Gear Box	Bonfiglioli
11	Driven Motor Make	Bonfiglioli

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost which will be 8-9% of total project amount.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd