**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**RP Tech Pvt Ltd**
308, Sector 7, PCNTDA, Bhosari, Pune 411026.

**Project, Location : Bhosari, Pune**

**Date :** 15.1.2021
**Quote NO :** SQT.20.21.2947
**Kind Attn :** Harshvardhan Saraf
**Email Id :** saraf.hp@creativecarve.com
**Contact No:** 9822049981

**Subject : Quotation for Sectional Door Horizontal Lift (Standard)**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Sectional Door Horizontal Lift** | 3400 | 4700 | 1 | 340,000 | 340,000 | 20,000 | 20,000 |
| | **Total** | | | **1** | | **340,000** | | **20,000** |
| 2 | P&F Charges | | | 3% | | 10,200 | | |
| | **Total Without Taxes** | | | | | 350,200 | | 20,000 |
| | GST Extra @ 18% | | | 18% | | 63,036.00 | | 3,600 |
| | **Total With Taxes** | | | | | **413,236** | | **23,600** |
| 3 | Transportation Charges | | | | | Extra at atcual | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Sectional Door - Horizontal Lift (Standard)**

| Sr. No | Specification | Sectional Door |
|---|---|---|
| 1 | **Vision Windows** | central panel |
| 2 | **Opening Direction & Mounting** | Horizontal lift (Standard) |
| 3 | **Opening/Closing Speed** | CDM9 0,28 m/s |
| 4 | **Door Material** | GI Steel |
| 5 | **Panel Thickness** | 42 mm Square Grid, steel sheet |
| 6 | **Filling** | CFC-free polyurethane |
| 7 | **Panel colour** | RAL 9002 Grey White Powder coated |
| 8 | **Door sealent** | All door sealants made of EPDM rubber, temperature resistant - 30/+70 |
| 9 | **Panel Flame Retardent standrad** | Flame retardant polyurethane foam according DIN4102-class B2. |
| 10 | **Water Penetration** | EN 12425 class 3 |
| 11 | **Air Permealibity** | EN12426 class 3 |
| 12 | **Wind Load** | EN21424 class 3 |
| 13 | **Thermal Transittance** | EN 12428 1.10W /m2K |
| 14 | **Bottom sealing** | Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber |
| 15 | **Door saftey** | Doors equiped with spring break device |
| 16 | **Incase of Power failuer** | Doors to be equiped with quick release fuction |
| 17 | **Operator power conumption** | Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W |
| 18 | **Drive Unit & Mounting Type** | Single phase 230V direct drive on shaft |
| 19 | **Emergency Operation** | by Disengagement rope manual |
| 20 | **Operating Switch** | Up/Down Keypad + stopbutton |
| 21 | **Locks : Lock bolt** | The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside. |
| 22 | **Environmental Green Product Declaration Certification** | As per ISO 14025 and EN 15804 |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | NIHVA |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 40% Advance along with Confirmed Purchase Order & 55% Balance before dispatch and 5% after Installation.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd