**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**RATILAL BHAGWANDAS CONSTRUCTION COMPANY**
Pune

**Date :** 18.11.2020
**Quote NO :** SQT.20.21.2829
**Kind Attn :** Sanjay Mulay
**Email Id :** rbcc.office1@gmail.com
**Contact No:** 9881196056

**Project Name & Location : Pirangut, Mulshi, Pune**

**Subject : Quotation for Motorized Sliding Gate, Telescopic Gate and Manual Swing Gate**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Motorised Single Leaf Sliding Gate | 8000 | 2500 | 1 | 441,000 | 441,000 | 20,000 | 20,000 |
| 2 | Automatic 2 Leaf Telescopic Sliding Gate | 8500 | 1500 | 1 | 490,000 | 490,000 | 20,000 | 20,000 |
| 3 | Manual Double Leaf Side Openable Gate | 8500 | 1500 | 1 | 217,000 | 217,000 | 20,000 | 20,000 |
| | | | **Total** | | | **1,148,000** | | **60,000** |
| 4 | P&F Charges | | | 3% | | 34,440 | | |
| | **Total Without Taxes** | | | | | 1,182,440 | | 60,000 |
| | GST Extra @ 18% | | | 18% | | 212,839.20 | | 10,800 |
| | **Total With Taxes** | | | | | **1,395,279** | | **70,800** |
| 5 | Transportation Charges | | | | | In Client Scope | | |
| 6 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Motorized Single Leaf Sliding Gate**

| Sr .No. | Specification | Motorized Single Leaf Sliding Gate |
|---|---|---|
| 1 | Door type | Motorized Single Leaf Sliding Gate |
| 2 | Opening Direction | Horizontal - from left to right or reverse |
| 3 | Mounting Location area | Inside area |
| 4 | Design Pattern | Standard Tubular Design Pattern |
| 5 | Outer Tube | 72 x 72 x 3.2mm MS SQ. TUBE |
| 6 | For Post | 72 x 72 x 3.2mm MS SQ. TUBE |
| 7 | Innear Tube | 38x38x3.20mm/40x40x3.2 MS SQ. TUBE |
| 8 | Gap Between Tubes | 125mm |
| 9 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 10 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| 11 | Guide Rollers supporter during Gate | Nylon Rollers with Bearings both side mounted on column for support smooth movement of |
| 12 | Painting | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| 13 | El motor make | BFT – Italy (100% imported) |
| 14 | Emergency Operation | Manual after turn the switch |
| 15 | Operating Switch | Push Button from inside |
| 16 | Safety | Photocells, Flashing Light |

**Automatic Double Leaf Telescopic Sliding Gate**

| Sr .No. | Specification | Telescopic Sliding Gate |
|---|---|---|
| 1 | Door type | Motorised Double Leaf Telescopic Sliding Gate |
| 2 | Clear Opening gate dimension | (W) 8500 mm X (H) 1500 mm |
| 6 | Opening Direction | Horizontal - from left to right or reverse |
| 7 | Mounting Location area | Inside area |
| 8 | Design Pattern | Standard Tubular Design Pattern |
| 9 | Outer Frame Tube Sizes | 72 x 72 x 3.2mm MS SQ. TUBE |
| 10 | Internal Vertical Tube Sizes | 25x25x3.20mm MS SQ. TUBE |
| 11 | For Post | 72 x 72 x 3.2mm MS SQ. TUBE |
| 12 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 13 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings |
| 14 | Guide Rollers supporter during Gate | Nylon Rollers with Bearings both side mounted on column for support smooth movement of |
| 15 | Painting | Two Coats of Primer and Two Coats of Synthetic Enamel Paint |
| 16 | Control Panel | 2 Nos Operating Station.( Motor Panel and Security Room) |
| 17 | Operation | By Telescopic Mechanism |
| 18 | Accessories | 1. Limit Switch for Cut out when Gate is fully Closed |
| | | 2. Flashing Light |
| | | 3. Remote |
| | | 4. Hooter |
| | | 5. Photocell |

**Manual Double Leaf Swing Gate**

| Sr .No. | Specification | Telescopic Sliding Gate |
|---|---|---|
| 1 | Clear Opening gate dimension | (W) 8.5 m x (H)1.5m |
| 2 | Opening Direction | Inside OR Outside |
| 3 | Mounting Location area | Inside |
| 4 | Max no of leafs | Double leaf (left hand & right hand) |
| 5 | Design Pattern | Standard Tubular Design Pattern |
| 6 | Outer Frame Tube Sizes | 80 x 80 x3.2 mm |
| 7 | Internal Vertical Tube Sizes | 40 x 40 x 2.0mm Placed at 100 mm |
| 8 | Bearing | Thrust bearing at bottom & ball bearing at top |
| 9 | Full Height Column sizes | 80 x 80 x 3.2 mm |
| 10 | Painting | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| 11 | Installation Checks | need to be check = space requirements + substructure + Mounting access + Access in the event of power cut |
| 12 | Civil work | Client scope – client need to grout the I beam in concrete to create track for sliding gate |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd