NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Retail Detailz (India) Pvt. Ltd.
211, 2nd Floor, R.R Realty,
Tank Road, Off LBS Marg
Bhandup(W), Mumbai - 400 078. INDIA

Date : 07.03.2020
Quote NO : SQT.19-20.2478R
Kind Attn : Mr. Pramol Awaghade
Email Id : purchase@orahretail.com
Contact No: 7738248754

Project Name & Location: Pune,

Subject : Revise offer . (Elevator type changed to Hydraulic Elevator from Electrical traction machine.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Depth (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GOODS LIFT**	2650	1950	1	1,250,000	1,250,000	20,000	20,000
				Total		**1,250,000**		**20,000**
2	P&F Charges			3%		**37,500**		
	Total Without Taxes					**1,287,500**		
	GST Extra @ 18%			18%		231,750		-
	Total With Taxes					**1,519,250**		**-**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications
1	**TYPE OF ELEVATOR - APPLICATION**	Goods
2	**Capacity**	1 ton
3	**TYPE OF ELEVATOR**	Hydraulic
4	**RATED LOAD IN KG**	1000
5	**RATED SPEED IN - m/s**	0.5
6	**ROPING**	2:01
7	**POWER SUPPLY**	3 Phase, 415 Volts, 50 Hz
8	**CONTROL**	Simplex Down Collective Control
9	**DRIVE**	V3F Drive
10	**FLOOR**	G+1
11	**ENTRANCE POSITION**	Same Side
12	**NOS. OF STOPS**	2
13	**NOS. OF OPENINGS**	2
14	**HEAD ROOM HEIGHT (mm)**	4000
15	**PIT DEPTH (mm)**	500
16	**TRAVEL (mm)**	5000
17	**CABIN SIZE**	CABIN SIZE : 1500 CABIN DEPTH (mm) : 1600
18	**LIFT DOOR SPECITIONS**	DOOR OPERATION : Manual DOOR OPENING (WIDTH x DEPTH) : 1500 W x 2000 H TYPE OF CAR DOOR : Manual Collapsible Door
19	**LIFT CABIN SPECITIONS**	CABIN WIDTH (mm) : 1500 CABIN DEPTH (mm) : 1600
20	**CAR AND LANDING OPERATING PANEL DISPLAY SPECITIONS**	COP & LOP TYPE : HALF LEGTH_SSHL_BOX TPES DISPLAY : Seven Segment Push Button Type / Touch Screen : Push Button Type
21	**ARD (Auto Rescue Device) system - In case of power failure, ARD system gets cabin to the nearest landing floor so that passengers can safely come out.**	
22	**Voice announcement system.**	
23	**Auto circuit for Cabin lights and fan.**	
24	**Digital position indicator in car & at all floors.**	
25	**Up/Down direction indicators in car & at all floors.**	
26	**Battery operated alarm bell.**	
27	**Door open bell.**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8-9 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333.**

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd