Sales Quotation

An ISO 9001:2008 Certified Company

Quotation No - SQT/19-20/1920R **Date : 16.08.2019**

RMK INFRASTRUCTURE PVT LTD
Talegaon

Kind Attn: Mr. Nagesh Sagar
Email: continental_billing@rmkinfrastructure.com
Mob.No. 7030967105

Project Name And Location :

Subject: Quotation for Rolling Shutter & HSD

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Price/Each	Net Amount INR
A	**Motorized Rolling Shutter**				
	Motorized Rolling Shutter Technical Specifications: • MS Slat : 1 mm Thick • Profile : Curved Type Profile with heavy duty Shaft • Hood Cover & Motor Cover : 0.9 mm Thick GI material • Gear Assembly • With Painting **(Supply + Installation)**				
1	Size: (W) 3000 mm X (H) 3000 mm	10	No	101,000	**1,010,000**
2	Size: (W) 5000 mm X (H) 4000 mm	4	No	169,000	**676,000**
3	Size: (W) 1500 mm X (H) 2250 mm	2	No	67,000	**134,000**
B	**Nihva Make Rapid Roll Up Door** **(Component Imported from Europe)** **(Supply + Installation)**				
Basic Equipment :	High-Speed Roller Door with PVC curtain.				
Drive Unit :	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Power supply :	3/(N)/PE/230/400/415 v; 50 Hz				
Safety :	Safety contact edge, Safety photocell transmitter / receiver inside side columns.				
Traffic Light:	Red & Green - Traffic light				
1	**Size : (W) 3000 mm x (H) 3000 mm**	1	No	342,000	342,000
2	**Size : (W) 1500 mm x (H) 2250 mm**	1	No	282,000	282,000

C	**BOOM Barrier (MICHELANGELO60 BT A U Made in Italy – 100% Imported)** **Each Boom Barrier Set include:** **MICHELANGELO BT A Barrier-1No.** **• Round Boom First part-1No.** **• Round Boom Second part- 1 No.** **• Anchor Base- 1No.** **• MOB. Boom Rest-1No.** **• Rubber Safety Profile- 1No.** **• OMEGA AT Acce. - 1No.** **• Transmitter with Channels- 1No.** **(Supply + Installation)**				
1	**Size- 6 Mtr MICHELANGELO60 BT A U**	2	No	150,000	300,000

SR No.	Specification	Boom Barrier
1	Control Unit	Libra C MV
2	Motor Power Supply	230Volt
3	opening or closing Time	6 sec
4	Type of Limit Swaitch	Electronic
5	Slowdown	Adjustable
6	Lock	Mechanical
7	Release	Personal Relese Key
8	Protection Rating	IP65

D	**AUTOMATIC SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate - (W) 9000 mm X (H) 1800 mm **• For Post- 72 x 72 x 3.2mm MS SQ. TUBE** **• Outer Frame- 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Frame - 38x38x3.20mm/40x40x3.2 MS SQ. TUBE** **• GAP BETWEEN INNER TUBES - 125 MM**				
1	**Size : (W) 9000 mm X (H) 1800 mm**	1	No	448,000	**448,000**

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places
3. Provide electrical cables near to the installation machinery
4. Hydra/crane at the time of Installation will be in NIHVA Scope.

Limit of Supply

1. Provide place to store the material to be installed
2. Be responsible for the safe custody of all material
3. Provide change & rest room for the workers

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Electrical connection for control panel

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. NIHVA Will provided structure drawing only if required
4. Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3% of total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 -6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with confirmed order, 20% before dispatch
6	**Taxes**	:	GST Extra @18%
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation.
8	**Warranty**	:	24 months from the date of supply

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** for any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti

7219206333

For NIHVA Technologies Pvt Ltd